

COMPLIANCE OF EC CONDITIONS of CLUSTER-VII

EC order no.: J-11015/238/2010-1A.II (M) Pt dated 12th October, 2018

(April'22 to September'22)

Sl.no.	Specific Conditions by MOEF:	Compliance
4 (i)	The project proponent shall obtain Consent to establish from the State Pollution Control Boards of Jharkhand for the proposed peak capacity of 11.42 MTPA prior to commencement of the increased production.	It is being complied. Consent to Establish has been obtained from JSPCB for the projects where production enhancement is planned/proposed.
4 (ii)	Transportation of coal from face to coal heap shall be carried out by truck. Further, the coal transportation from coal heap to Coal Handling Plant shall be carried out through covered trucks.	It is being complied. Presently coal transportation is being done by trucks covered with tarpaulin cover. Covering of trucks has been made mandatory in the transportation contract. Picture – 1.
4 (iii)	Mitigation measures to be undertaken to control dust and other fugitive emissions all along the roads by providing sufficient numbers of water sprinklers.	It is being complied. Mobile Water Sprinklers are being used for Sprinkling water on transportation roads. Additionally Manual Sweeping is done on Public roads on routine basis and Truck mounted fog Canon has also been procured. Picture – 2 & Picture - 3.
4 (iv)	Sufficient coal pillars shall be left un-extracted around the air shaft (within the subsidence influence area) to protect from any damage from subsidence, if any.	It is being complied. Sufficient coal pillars have been left around air shafts as per Coal Mines Regulations 2017 and DGMS Orders.
4 (v)	Solid barrier shall be left below the roads falling within the block to avoid any damage to the roads and no depillaring operation shall be carried out below the township/colony.	It is being followed. Sufficient barriers are left for saving the surface installation and infra structures as per Coal Mines regulation 2017 and DGMS Orders.
4 (vi)	Depression due to subsidence resulting in water accumulating within the low lying areas shall be filled up or drained out by cutting drains.	It is being complied. Time to time depression created by the mining operations have been filled by the locally available material and over burden.
4 (vii)	Sufficient number of pumps of adequate capacity shall be deployed to pump out mine water during peak rain fall.	It is being complied.
4 (viii)	The company shall obtain approval of CGWA for use of groundwater for mining operations at its enhanced capacity of 11.42 MTPA.	NOC for usage/extraction of Ground water is already granted for Cluster VII group of Mines. Copy of NOC enclosed as Picture - 4
4 (ix)	Continuous monitoring of occupational safety and other health hazards, and the corrective actions need to be ensured.	It is being Complied. Proper safety, health hazards and the corrective measures are being taken by Area and HQ Level Safety/Medical Board on regular basis. Periodical Medical Examination Report enclosed as Annexure – VI

4 (x)	The fire dealing operations by excavating out fire should be expedited.	It is being complied. Mining is being carried out by OC Method where UG fire is present with due permission from DGMS. Action is being taken to control, mine fires including old OB dump & areas as specified in Jharia Master Plan.
--------------	---	---

Generic Conditions by MOEF:

A. Mining		
i	Mining shall be carried out under strict adherence to provisions of the Mines Act 1952 and subordinate legislations made there-under as applicable.	It is being complied. All stipulated provisions and subordinate legislations are being followed.
ii	No change in mining method, calendar programme and scope of work shall be made without obtaining prior approval of the Ministry of Environment, Forest and Climate Change.	It is being Complied.
iii	Mining shall be carried out as per the approved mining plan including Mine Closure Plan, abiding by mining laws related to coal mining and the relevant circulars issued by Directorate General Mines Safety (DGMS).	It is being complied. Mining is being carried out abiding by mining laws and relevant circulars issued by DGMS. Mine Closure Plan, has been prepared for each Mine in this cluster. Progressive mine closure has been implemented regularly as per the approved Mine Closure Plan prepared by CMPDIL.
iv	No mining shall be carried out in forest land without obtaining Forestry Clearance as per Forest (Conservation) Act, 1980 and also adhering to The Scheduled Tribes and Other Traditional Forest Dwellers (Recognition of Forest Rights) Act, 2006 read with provisions of Indian Forest Act, 1927.	It is being Complied.
B. Land reclamation and water conservation		
i	Digital Survey of entire lease hold area/core zone using Satellite Remote Sensing survey shall be carried out at least once in three years for monitoring land use pattern and report in 4:50000 scale shall be submitted to Ministry of Environment, Forest and Climate Change/Regional Office (RO).	It is being complied. Land Use Map of Cluster VII has been prepared by CMPDIL using remote sensing data for monitoring of land use pattern and for post mining land use. The land use map is attached in Annexure I .

ii	The surface drainage plan including surface water conservation plan for the area of influence affected by the said mining operations, considering the presence of river/rivulet/pond/lake etc, shall be prepared and implemented by the project proponent. The surface drainage plan and/or any diversion of natural water courses shall be as per the approved Mining Plan/EIA/EMP report and with due approval of the concerned State/Gol Authority. The construction of embankment to prevent any danger against inrush of surface water into the mine should be as per the approved Mining Plan and as per the permission of DGMS.	It is being complied. The surface drainage plan and/or any diversion of natural water courses shall be as per the approved Mining Plan/EMP report. Approval from competent authority of State Govt. shall be sought in case of diversion of Natural Water Course. Embankment has been constructed in some areas and further embankment and stone pitching work will be carried out.
iii	The final mine void depth should preferably be as per the approved Mine Closure Plan, and in case it exceeds 40 m, adequate engineering interventions shall be provided for sustenance of aquatic life therein. The remaining area shall be backfilled and covered with thick and alive top soil. Post-mining land be rendered usable for agricultural/forestry purposes and shall be handed over to the respective state government as specified in the guidelines for Preparation of Mine Closure Plan issued by the Ministry of Coal dated 27th August, 2009 and subsequent amendments.	It is being complied. ▪ Backfilling process in abandoned pits and voids are continuously carried out along with the mining operation. ▪ Ecological restoration and Plantation shall be carried out on finalization of dumps. ▪ Abandoned Pits will be utilized for Pisciculture in Post Mining Phase.
iv	The entire excavated area, backfilling, external OB dumping (including top soil) and afforestation plan shall be in conformity with the “during mining”/“post mining” land-use pattern, which is an integral part of the approved Mining Plan and the EIA/EMP submitted to this Ministry. Progressive compliance status vis-a-vis the post mining land use pattern shall be submitted to the Ministry of Environment, Forest and Climate Change/Regional Office on six monthly basis.	It shall be complied.
V	The top soil shall temporarily be stored at earmarked site(s) only and shall not be kept unutilized for long. The top soil shall be used for land reclamation and plantation purposes. Active OB dumps shall be stabilized with native grass species to prevent erosion and surface run off. The other overburden dumps shall be vegetated with native flora species. The excavated area shall be backfilled and afforested in line with the approved Mine Closure Plan. Monitoring and management of rehabilitated areas shall continue until the vegetation becomes self-sustaining. Compliance status shall be submitted to the Ministry of Environment, Forest and Climate Change/ Regional Office on six monthly basis.	It is being complied. Top soil dumps have been created separately. Top soil is spread over Slopes of OB Dumps, used in plantation activities. Top soil is spread over slopes of OB dumps and grass seed balls are thrown over it for grassing. Once the OB dump reaches its final stage it would be taken up for Three tier plantation and eco-restoration. Native flora species would be planted in these sites during eco - restoration Picture – 6, 8 & 11.

C. Emissions, effluents, and waste disposal

i	Transportation of coal, to the extent permitted by road, shall be carried out by covered trucks/conveyors. Effective control measures such as regular water/mist sprinkling/rain gun etc shall be carried out in critical areas prone to air pollution (with higher values of PM10/PM2.5) such as haul road, loading/unloading and transfer points. Fugitive dust emissions from all sources shall be controlled regularly. It shall be ensured that the Ambient Air Quality parameters conform to the norms prescribed by the Central/State Pollution Control Board.	It is being complied. Presently coal transportation is being done by trucks covered with tarpaulin cover. Covering of truck has been made mandatory in the transportation contracts. Mobile Water Sprinklers are being used for mitigating dust from being air borne from haul roads. Manual sweeping of Public roads used for transportation is being done on routine basis. Picture – 1 & 2
ii	Greenbelt consisting of 3-tier plantation of width not less than 7.5 m shall be developed all along the mine lease area in a phased manner. The green belt comprising a mix of native species shall be developed all along the major approach/ coal transportation roads.	It shall be complied. 3-tier plantation shall be developed along mine lease area in available spaces in a phased manner. Green belt along final transportation roads shall be developed.
iii	The transportation of coal shall be carried out as per the provisions and route proposed in the approved Mining Plan. Transportation of the coal through the existing road passing through any village shall be avoided. In case, it is proposed to construct a 'bypass' road, it should be so constructed so that the impact of sound, dust and accidents could be appropriately mitigated.	It is being complied.
iv	Vehicular emissions shall be kept under control and regularly monitored. All the vehicles engaged in mining and allied activities shall operate only after obtaining 'PUC' certificate from the authorized pollution testing centers.	It is being complied. Vehicles used for transportation of coal are covered by tarpaulin cover and are monitored for the vehicular emission by the transporter and BCCL. Copy of some Pollution Under Control Certificates has been enclosed as Annexure II .
v	Coal stock pile/crusher/feeder and breaker material transfer points shall invariably be provided with dust suppression system. Belt-conveyors shall be fully covered to avoid air borne dust. Side cladding all along the conveyor gantry should be made to avoid air borne dust. Drills shall be wet operated or fitted with dust extractors.	It is being complied. Crushers/feeders breakers are fitted with water sprinklers Coal handling plant are enclosed with metal sheets and are fitted with water sprinklers to check fugitive emissions. Picture - 7
vi	Coal handling plant shall be operated with effective control measures viz. bag filters/water or mist sprinkling system etc. to check fugitive emissions from crushing operations, conveyor system, transfer points, etc.	It is being complied. Coal handling plant are enclosed with metal sheets and are fitted with water sprinklers to check fugitive emissions. Picture - 7

vii	Ground water, excluding mine water, shall not be used for mining operations. Rainwater harvesting shall be implemented for conservation and augmentation of ground water resources.	It is being complied. Mine water is being used for the industrial as well as domestic purpose. Mine water is also supplied to colonies and community after filtration through pressure filters, slow sand filters and rapid sand filters. Proposal for mine water supply to nearby village/community is taken up under CSR Policy of the company. Rain Water Harvesting is being implemented in phased manner. A MoU has been signed between Coal India Ltd. & Govt. of Jharkhand for providing mine water to nearby villages. A copy of MoU has been enclosed as Annexure III .
viii	Catch/garland drains and siltation ponds of appropriate size shall be constructed around the mine working, coal heaps & OB dumps to prevent run off of water and flow of sediments directly into the river and water bodies. Further, dump material shall be properly consolidated/ compacted and accumulation of water over dumps shall be avoided by providing adequate channels for flow of silt into the drains. The drains/ ponds so constructed shall be regularly de- silted particularly before onset of monsoon and maintained properly. Sump capacity should provide adequate retention period to allow proper settling of silt material. The water so collected in the sump shall be utilized for dust suppression measures and green belt development. Dimension of the retaining wall constructed, if any, at the toe of the OB dumps within the mine to check run-off and siltation should be based on the rainfall data. The plantation of native species to be made between toe of the dump and adjacent field/habitation/water bodies.	It is being complied. In phased manner, garland drains are constructed around mine working, coal heaps & OB dumps to prevent run off water and flow of sediments directly into the river & water bodies.
ix	Industrial waste water generated from CHP, workshop and other waste water, shall be properly collected and treated so as to conform to the standards prescribed under the Environment (Protection) Act, 1986 and the Rules made there under, and as amended from time to time. Oil and grease trap shall be installed and maintained fully functional with effluents discharge adhering to the norms. Sewage treatment plant of adequate capacity shall be installed for treatment of domestic waste.	It is being complied. Effluents discharge standards are regularly monitored by CMPDIL for cluster VII group of mines. Mine water is being treated using filter plants (Pressure, Sand filters etc.) for its further use in industrial purpose and supply to the residential areas. Mine water monitoring report has been enclosed as Annexure IV . Oil & grease Trap has been installed. Picture 10
x	Adequate groundwater recharge measures shall be taken up for augmentation of ground water. The project authorities shall meet water requirement of nearby village(s) in case the village wells go dry due to dewatering of mine.	It is being complied. Rain Water Harvesting is being constructed clusterwise. Mine water is also supplied to colonies and community after filtration through pressure filters, slow sand filters and rapid sand filters.

D. Illumination, Noise & Vibration		
i	Adequate illumination shall be ensured in all mine locations (as per DGMS standards) and monitored weekly. The report on the same shall be submitted to this ministry & it's RO on six-monthly basis.	It is being complied. Adequate illumination is being ensured in all mine locations as per DGMS standards and the same is being monitored by Area & HQ Level Safety Committees on regular basis.
ii	Adequate measures shall be taken for control of noise levels below 85 dB(A) in the work environment. Workers engaged in blasting and drilling operations, operation of HEMM, etc shall be provided with personal protective equipments (PPE) like ear plugs/muffs in conformity with the prescribed norms and guidelines in this regard. Adequate awareness programme for users to be conducted. Progress in usage of such accessories to be monitored.	It is being complied. Personnel operating HEMMs, drilling machine and other machines comply with safety regulation and are equipped. Noise monitoring data has been enclosed as Annexure V .
iii	Controlled blasting techniques shall be practiced in order to mitigate ground vibrations and fly rocks as per the guidelines prescribed by the DGMS.	It is being complied. DGMS regulations are followed strictly for blasting. Additionally Personnel operating HEMMs, drilling machine and other machines are given training on regular basis.
iv	The noise level survey shall be carried out as per the prescribed guidelines to assess noise exposure of the workmen at vulnerable points in the mine premises, and report in this regard shall be submitted to the Ministry/RO on six-monthly basis.	It is being complied. Noise level monitoring is done by CMPDIL on monthly basis. Noise monitoring data has been enclosed as Annexure V .
E. Occupational health & safety		
i	The project proponent shall undertake occupational health survey for initial and periodical medical examination of the workers engaged in the project and maintain records accordingly as per the provisions of the Mines Rules, 1955 and DGMS circulars. Besides regular periodic health check-up, 20% of the workers identified from workforce engaged in active mining operations shall be subjected to health check-up for occupational diseases and hearing impairment, if any.	It is being complied. Initial and Periodical Medical Examination (PME) of all the mining and other personnel is being carried out regularly at Area Hospital, as per the Statutes and guidelines of Director General of Mines Safety (DGMS). Enclosed as Annexure VI .
ii	Personnel (including outsourcing employees) working in dusty areas shall wear protective respiratory devices and shall also be provided with adequate training and information on safety and health aspects.	It is being complied. Protective respiratory devices & other PPEs are supplied to personnel working in dusty areas. Also, a separate full-fledged Human Resource Development (HRD) Department is conducting regular training programme on these issues. Apart from this Vocational Training Centers (VTCs) are existing in all the Areas of BCCL, which provides periodical training on the safety and occupational health issue to the workers.

iii	Skill training as per safety norms specified by DGMS shall be provided to all workmen including the outsourcing employees to ensure high safety standards in mines.	It is being complied. HRD Department & Area level Vocational Training Centers are conducting regular training programs. Status of training enclosed as Annexure VII. Picture - 5
-----	---	--

F. Ecosystem and biodiversity conservation

i	The project proponent shall take all precautionary measures during mining operation for conservation and protection of endangered flora/fauna, if any, spotted/reported in the study area. The Action plan in this regard, if any, shall be prepared and implemented in consultation with the State Forest and Wildlife Department.	It is being complied. Conservation and Protection of endangered flora/fauna shall be taken with utmost priority if spotted/reported. Action Plan shall be prepared in consultation with State Forest and Wildlife Department.
---	---	--

G. Public hearing, R&R and CSR

i	Implementation of the action plan on the issues raised during the public hearing shall be ensured. The project proponent shall undertake all the tasks/measures as per the action plan submitted with budgetary provisions during the public hearing. Land ousters shall be compensated as per the norms laid down in the R&R policy of the company/State Government/Central Government, as applicable.	It is being complied. The issues raised during Public Hearing is mentioned in the EMP and phase wise measures are being taken to ensure its implementation.
ii	The project proponent shall ensure the expenditure towards socio-economic development in and around the mine, in every financial year as per the Corporate Social Responsibility Policy as per the provisions under Section 135 of the Companies Act, 2013	It is being complied. BCCL is implementing CSR activities at various scale. A separate CSR committee has been formed at area level, which is looking after the works being executed under CSR. Various activities under CSR were undertaken during COVID-19 viz. distribution of masks, hand sanitisers, gloves, soap, food packets, etc
iii	The project proponent shall follow the mitigation measures provided in this Ministry's OM No.Z-11013/5712014-IA.11 (M) dated 29" October, 2014, titled 'Impact of mining activities on habitations-issues related to the mining projects wherein habitations and villages are the part of mine lease areas or habitations and villages are surrounded by the mine lease area'.	It shall be complied. Rehabilitation of project affected families is being done as per Approved Master Plan for Jharia Coalfields.

iv	The project proponent shall make necessary alternative arrangements, if grazing land is involved in core zone, in consultation with the State government to provide alternate areas for livestock grazing, if any. In this context, the project proponent shall implement the directions of Hon'ble Supreme Court with regard to acquiring grazing land.	It shall be complied.
-----------	--	-----------------------

H. Corporate Environment Responsibility

i	The Company shall have a well laid down environment policy duly approved by Board of Directors. The environment policy should prescribe for standard operating procedures to have proper checks and balances and to bring into focus any infringements/deviation/violation of the environmental or forest norms/conditions. Also, the company shall have a defined system of reporting of non-compliances/violations of environmental norms to the Board of Directors and/or shareholders/stakeholders.	A well-defined Corporate Environment Policy has already been laid down and approved by the Board of Directors. This is also uploaded on company's website. Enclosed as Annexure IX .
ii	The project proponent shall comply with the provisions contained in this Ministry's OM dated 1 st May, 2018, as applicable, regarding Corporate Environment Responsibility	It shall be complied.
iii	The hierarchical system or Administrative Order of the company to deal with environmental issues and for ensuring compliance with the environmental clearance conditions should be displayed on website of the Company.	It is being complied. A hierarchical system of the company to deal with environmental issues from corporate level to mine level already exists.
iv	A separate environmental management cell both at the project and company headquarter level, with suitable qualified personnel shall be set-up under the control of a Senior Executive, who will report directly to the Head of the Organization.	Complied. - A full-fledged Environment Department, headed by a Dy.GM (Environment) along with a suitable qualified multi-disciplinary team of executives have been established at Company Headquarters for implementation of Environment Policy of the company. - One Executive in each area has also been nominated as Nodal Officer (Environment) for looking after routine environment related jobs along with an Environment Management Cell at Area Level. - For implementing and look after Socio-Economic Issues, an executive of Community Development Cadre is also posted at area level.

v	Action plan for implementing EMP and environmental conditions shall be prepared and shall be duly approved by competent authority. The year wise funds earmarked for environmental protection measures shall be kept in separate account and not to be diverted for any other purpose. Year wise progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six Monthly Compliance Report.	It is being complied.
vi	Self-environmental audit shall be conducted annually. Every three years third party environmental audit shall be carried out.	Internal audit is done periodically and third party audit shall be done by ICFRE soon.

I. Statutory Obligations

i	The environmental clearance shall be subject to orders of Hon'ble Supreme Court of India, Hon'ble High Court, NGT and any other Court of Law from time to time, and as applicable to the project.	Agreed
ii	This environmental clearance shall be subject to obtaining wildlife clearance, if applicable, from the Standing Committee of National Board for Wildlife.	Agreed
iii	The project proponent shall obtain Consent to Establish/Operate under the Air Act, 1981 and the Water Act, 1974 from the concerned State Pollution Control Board.	Complied.
iv	The project proponent shall obtain the necessary permission from the Central Ground Water Authority. (CGWA).	Agreed. Application for obtaining NOC for usage/extraction of Ground water is already submitted to CGWA for Cluster VII group of Mines. Picture 4

J. Monitoring of project

i	Adequate ambient air quality monitoring stations shall be established in the core zone as well as in the buffer zone for monitoring of pollutants, namely PM ₁₀ , PM _{2.5} , SO _x and NO _x . Location of the stations shall be decided based on the meteorological data, topographical features and environmentally and ecologically sensitive targets in consultation with the State Pollution Control Board. Online ambient air quality monitoring stations may also be installed in addition to the regular monitoring stations as per the requirement and/or in consultation with the SPCB. Monitoring of heavy metals such as Hg, As, Ni, Cd, Cr, etc to be carried out at least once in six months.	It is being complied. Regular Monitoring is being carried out by CMPDIL. Tender for COAAQMS was already floated, technical and financial scrutiny is going on the bids submitted. Establishment of ambient environment quality monitoring stations has been finalized with the consultation of Jharkhand State Pollution Control Board. Enclosed in Annexure X.
----------	---	--

ii	The Ambient Air Quality monitoring in the core zone shall be carried out to ensure the Coal Industry Standards notified vide GSR 742 (E) dated 25.9.2000 and as amended from time to time by the Central Pollution Control Board. Data on ambient air quality and heavy metals such as Hg, As, Ni, Cd, Cr and other monitoring data shall be regularly reported to the Ministry/Regional Office and to the CPCB/SPCB.	It is being complied. Data is regularly submitted to ministry along with compliance report. Ambient Air Quality monitoring report attached as Annexure XI .
iii	The effluent discharge (mine waste water, workshop effluent) shall be monitored in terms of the parameters notified under the Coal Industry Standards vide GSR 742 (E) dated 25.9.2000 and as amended from time to time by the Central Pollution Control Board.	It is being complied. Effluents discharge standards are regularly monitored by CMPDIL for cluster VII group of mines. Mine water is being treated using filter plants (Pressure, Sand filters etc.) for its further use in industrial purpose and supply to the residential colonies. Mine water monitoring report has been enclosed as Annexure IV .
iv	The monitoring data shall be uploaded on the company's website and displayed at the project site at a suitable location. The circular No. J-20012/1/2006-IA.11 (M) dated 27.05.2009 issued by Ministry of Environment, Forest and Climate Change shall also be referred in this regard for its compliance.	It is being Complied.
v	Regular monitoring of ground water level and quality shall be carried out in and around the mine lease area by establishing a network of existing wells and constructing new piezometers during the mining operations. The monitoring of ground water levels shall be carried out four times a year i.e. pre-monsoon, monsoon, post-monsoon and winter. The ground water quality shall be monitored once a year, and the data thus collected shall be sent regularly to Ministry of Environment, Forest and Climate Change/Regional Office.	Compliance under progress. Drilling of Piezometric well has been completed and DWLR is being procured for monitoring of Ground Water level. Picture-12. CMPDI is regularly conducting study of groundwater level and quality of areas within Cluster VII. Groundwater monitoring data has been enclosed as Annexure XII.
vi	Monitoring of water quality upstream and downstream of water bodies shall be carried out once in six months and record of monitoring data shall be maintained and submitted to the Ministry of Environment, Forest and Climate Change/Regional Office.	It is being complied. CMPDI RI-II is regularly conducting study water quality. Water Quality report attached as Annexure IV .
vii	The project proponent shall submit six monthly reports on the status of the implementation of the stipulated environmental conditions to the Ministry of Environment, Forest and Climate Change/Regional Office. For half yearly monitoring reports, the data should be monitored for the period of April to September and October to March of the financial years.	It is being complied.

viii	The Regional Office of this Ministry shall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer (s) of the Regional Office by furnishing the requisite data / information/monitoring reports.	Agreed.
K. Miscellaneous		
i	Efforts should be made to reduce energy consumption by conservation, efficiency improvements and use of renewable energy.	It is being complied. Conventional bulbs are being replaced by LED bulbs in official/industrial premises. Energy efficient High Mast Lighting towers, energy efficient fans are being procured replacing the old ones. Solar Energy is also being harnessed at HQ level.
ii	The project authorities shall inform to the Regional Office regarding commencement of mining operations.	Agreed.
iii	A copy of the environmental clearance shall be marked to concerned Panchayat. A copy of the same shall also be sent to the concerned State Pollution Control Board, Regional Office, District Industry Sector and Collector's Office/Tehsildar Office for information in public domain within 30 days.	It has been complied.
iv	The EC shall be uploaded on the company's website. The compliance status of the stipulated EC conditions shall also be uploaded by the project authorities on their website and updated at least once every six months so as to bring the same in public domain.	It has been complied.
v	The project authorities shall advertise at least in two local newspapers widely circulated, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of this clearance, informing that the project has been accorded environmental clearance and a copy of the same is available with the State Pollution Control Board and also at website of the Ministry.	It has been complied. Enclosed in Annexure XIII.
vi	The environmental statement for each financial year ending 31 March in Form-V is mandated to be submitted by the project proponent for the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be uploaded on the Company's website along with the status of compliance of EC conditions and shall be sent to the respective Regional Offices of the MoEF&CC by e-mail. Concerns raised during public hearing.	It is being complied. EC Compliance is regularly updated on company's website.

vii	The above conditions will be enforced inter-alia, under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and the Public Liability Insurance Act, 1991 along with their amendments and Rules and any other orders passed by the Hon'ble Supreme Court of India/High Courts and any other Court of Law relating to the subject matter.	Agreed
------------	--	---------------

COMPLIANCE OF ADDITIONAL EC CONDITIONS of CLUSTER-VII
EC order no.: J-11015/238/2010-1A.II (M) Pt dated 20th August, 2020

Sl.no.	Conditions by MOEF:	Compliance
(i)	Mitigating measures shall be undertaken to control dust and other fugitive emissions all along the roads by providing sufficient water sprinklers. Adequate corrective measures shall be undertaken to control dust emissions, which would include mechanized sweeping, water sprinkling/mist spraying on haul roads and loading sites, long range misting/fogging arrangement, wind barrier wall and vertical greenery system, green belt, dust suppression, arrangement at loading and unloading points, etc.	It is being complied. Mobile Water Sprinklers are being used for Sprinkling water on transportation roads. Picture - 2 Additionally Manual Sweeping is done on Public roads on routine basis. Truck mounted fog canon has also been procured and is in operation. Picture - 3 Green belt is being development along railway sidings. Picture - 7
(ii)	Continuous monitoring of occupational safety and other health hazards, and the corrective actions needs to be ensured.	It is being Complied. Proper safety, health hazards and the corrective measures are being taken by Area and HQ Level Safety/Medical Board on regular basis
(ii)	Persons of nearby villages shall be given training on livelihood and skill development to make them employable.	It is being complied. Company is organizing training on regular basis through Vocational Training Centre and Human Resource Department. Also skill development for PAPs is being undertaken. Picture 13
(iv)	Thick green belt of adequate width at the final boundary in the downwind direction of the project site shall be developed to mitigate/check dust pollution.	It shall be complied.
(v)	Efforts shall be made for utilizing alternate sources of surface water, abandoned mines or else whatsoever and thus minimizing dependability on a single source.	It is being complied. Mine water is being used for the industrial as well as domestic purpose. Mine water is also supplied to colonies and community after filtration through pressure filters, slow sand filters and rapid sand filters. Rain Water Harvesting is being implemented in phased manner.
(vi)	Continuous monitoring of occupational safety and other health hazards, and the corrective actions	It is being Complied. Proper safety, health hazards and the corrective measures are being taken by Area


	needs to be ensured.	and HQ Level Safety/Medical Board on regular basis
(vii)	A third party assessment of EC compliance shall be undertaken once in three years through reputed Government Institutes or any other expert agency identified by the Ministry.	It shall be Complied. Third party audit shall be done by ICFRE soon.
(viii)	Active OB Dump should not be kept barren/open and should be covered by temporary grass to avoid air borne of particles.	It is being complied. Grass seed balls are spread over slopes of active OB Dumps. Picture – 6 (OB Dump Pic)
(ix)	Project Proponent shall obtain blasting permission from DGMS for conducting mining operation near villages and explore deployment of rock breakers of suitable capacity in the project to avoid blasting very near to villages. There shall be no damages caused to habitations/structures due to blasting activity.	It is being complied.
(x)	The Project proponent shall comply with all the statutory requirements and judgement of Hon'ble Supreme Court dated 2 nd August 2017 in Writ Petition (Civil) No. 114 of 2014 in the matter of Common Cause versus Union of India and Ors. State Government shall ensure that the entire compensation levied, if any, for illegal mining paid by the Project Proponent through their respective Department in strict compliance of judgement of Hon'ble Supreme Court dated the 2 nd August 2017 in Writ Petition (Civil) No. 114 of 2014 in the matter of Common Cause versus Union of India and Ors.	Agreed.
(xi)	Proponent shall appoint an Occupational Health Specialist for Regular and Periodical medical examination of the workers engaged in the Project and maintain records accordingly; also, Occupational health check-ups for workers having some ailments like BP, diabetes, habitual smoking, etc. shall be undertaken once in six months and necessary remedial/preventive measures taken accordingly. The recommendations of National Institute for ensuring good occupational environment for mine workers shall be implemented; The prevention measures for burns, malaria and provision of anti-snake venom including all other paramedical safeguards may be ensured before initiating the mining activities.	It is being complied. Initial and Periodical Medical Examination (PME) of all the mining and other personnel is being carried out regularly at Area Hospital, as per the Statutes and guidelines of Director General of Mines Safety (DGMS). Report attached as Annexure VI.
(xii)	Project proponent shall follow the mitigation measures provided in Office Memorandum No. Z-11013/57/2014-IA.II (M), dated 29 th October, 2014, titled “ Impact of mining activities on Habitations- Issues related to the mining Projects wherein Habitations and villages are the part of mine lease areas or habitations and the village are surrounded by the mine lease area.”	Agreed.
(xiii)	The illumination and sound at night at project sites disturb the villages in respect of both human and animal population. Consequent sleeping disorders and stress may affect the health in the	It is being followed.

	villages located close to mining operations. Habitations have a right for darkness and minimal noise levels at night. PPs must ensure that the biological clock of the villages is not disturbed; by orienting the floodlights/masks away from the villagers and keeping the noise levels well within the prescribed limits for day light/night hours.	
(xiv)	The project proponent shall take all precautionary measures during mining operation for conservation and protection of endangered fauna, if any, spotted in the study area. Action plan for conservation of flora and fauna shall be prepared and implemented in consultation with the State Forest and Wildlife Department. A copy of action plan shall be submitted to the Ministry of Environment, Forest and Climate Change and its Regional Office.	It shall be complied if any endangered fauna spotted.
(xv)	Hon'ble Supreme Court in a Writ Petition(s) Civil No. 114/2014, Common Cause v Union of India & Ors vide its judgment dated 8 th January, 2020 has directed the Union of India to impose a condition in the mining lease and similar condition in the environmental clearance and the mining plan to the effect that the mining lease holders shall, after ceasing mining operations, undertake re-grassing the mining area and any other area which may have been disturbed due to their mining activities and restore the land to a condition which is fit for growth of fodder, flora, fauna, etc. Compliance of this condition after the mining activity is over at the cost of the mining lease holders/Project Proponent". The implementation report of the above said condition shall be sent to Regional Office of the MoEFCC.	It shall be complied.




Project Officer

Ena OC



Project Officer

ADIC



Project Officer

Rajapur/S-Jharia



Project Officer

Kusunda OC



Project Officer

AEBSC



Project Officer

Bhutgoria UG



Project Officer

Alkusa UG



Project Officer

Burragarh UG



Project Officer


Hurriladih UG



Project Officer

Kustore UG

LAND USE / LAND COVER MAP OF THE CLUSTER-VII MINES, BCCL



Sl no	Land Use Details	Existing (sq. meter)	Proposed (sq. meter)	Grand Total (sq. meter)
1	Green Belt Area	968.53 x 10 ⁴	968.53 x 10 ⁴	968.53 x 10 ⁴
2	Open Land	746.72 x 10 ⁴	746.72 x 10 ⁴	746.72 x 10 ⁴
3	Road/ Paved Area	380.73 x 10 ⁴	380.73 x 10 ⁴	380.73 x 10 ⁴
4	Rooftop area of building/ sheds	31.71 x 10 ⁴	31.71 x 10 ⁴	31.71 x 10 ⁴
5	Total	2127.70 x 10 ⁴	2127.70 x 10 ⁴	2127.70 x 10 ⁴

[See rules 115 (2)]

Pollution Under Control Certificate

Authorised By :
Government of Jharkhand

Date : 19/04/2022
Time : 17:08:39 PM
Validity upto : 18/10/2022

Certificate SL. No. : JH01001710008008
Registration No. : JH10AM4763
Date of Registration : 28/Nov/2013
Month & Year of Manufacturing : November-2013
Valid Mobile Number : *****6337
Emission Norms : BHARAT STAGE III
Fuel : DIESEL
PUC Code : JH0100171
GSTIN :
Fees :
MIL observation : Rs.300.00(GST as applicable)
No

Vehicle Photo with Registration plate
60 mm x 30 mm



Sr. No.	Pollutant (as applicable)	Units (as applicable)	Emission limits	Measured Value (upto 2 decimal places)
1	2	3	4	5
Idling Emissions	Carbon Monoxide (CO)	percentage (%)		
	Hydrocarbon, (THC/HC)	ppm		
High idling emissions	CO	percentage (%)		
	RPM	RPM	2500 ± 200	
	Lambda	-	1 ± 0.03	
Smoke Density	Light absorption coefficient	1/metre	2.45	2.23

This PUC certificate is system generated through the national register of motor vehicles and does not require any signature.

Note : 1. Vehicle owners to link their mobile numbers to registered vehicle by logging to <https://vahan.parivahan.gov.in>

[See rules 115 (2)]


Under Control Certificate

Issued By
Department of Jharkhand
Date : 12/09/2021
Time : 11:21:37 AM
Validity upto : 11/09/2022



Certificate SL No : JH01000670000187
Registration No : JH10B15131
Date of Registration : 04/Dec/2018
Month & Year of Manufacturing : October-2018
Valid Mobile Number : *****1392
Emission Norms : BHARAT STAGE IV
Fuel : DIESEL
PUC Code : JH0100067
GSTIN :
Fees : Rs.300.0(GST as applicable)
MIL observation : No

Vehicle Photo with Registration plate
60 mm x 30 mm



Sr. No.	Pollutant (as applicable)	Units (as applicable)	Emission limits	Measured Value (upto 2 decimal places)
1	2	3	4	5
Idling Emissions	Carbon Monoxide (CO)	percentage (%)		
	Hydrocarbon, (THC/HC)	ppm		
High Idling emissions	CO	percentage (%)		
	RPM	RPM	2500 $\pm$ 200	
	Lambda		1 $\pm$ 0.03	
Smoke Density	Light absorption coefficient	1/metre	1.62	0.08

This PUC certificate is system generated through the national register of motor vehicles and does not require any signature.

Note : 1. Vehicle owners to link their mobile numbers to registered vehicle by logging to <https://vahan.parivahan.gov.in>

Authorised Signature with stamp of PUC operator
(Optional for State)
60mm x 20 mm

Memorandum of Understanding

for

Utilization of mine water by villages situated near mines of CIL in command area of Central Coalfields Limited, Bharat Coking Coal Limited and Eastern Coalfields Limited in the State of Jharkhand

This Memorandum of Understanding "MoU" ("Agreement") is made on 30th day of October 2017 at Ranchi

By and Between

Government of Jharkhand (hereinafter referred to as "GoJ"), represented through Department of Industries, Mines & Geology and Department of Drinking Water & Sanitation, Government of Jharkhand having its office at Ranchi which expression shall, unless the context otherwise requires, includes its successors and assignees of the FIRST PART;

And

Coal India Limited (hereinafter referred to as "CIL"), a Government of India Enterprise having its Registered Office at Coal Bhawan, Premise No-04 MAR, Plot No- AF-III, Action Area- 1A, Newtown, Rajarhat, Kolkata- 700156 and represented by General Manager, Corporate Social Responsibility, which expression shall, unless repugnant to the context or meaning thereof, be deemed to include its successors, and permitted assignees of the SECOND PART;

The expressions GoJ and CIL shall hereinafter, as the context may admit or require, be individually referred to as the 'The Party' and collectively as 'the Parties'.

Whereas:

- A.** The Government of Jharkhand (GoJ) and Coal India Limited (CIL), both parties have agreed in principle to the objective of achieving the common goal of providing surplus water from suitable mines for use by habitations, located in the command area of subsidiaries of CIL in the state of Jharkhand for their various needs. These subsidiaries are Central Coalfields Limited (CCL), Bharat Coking Coal Limited (BCCL) and Eastern Coalfields Limited (ECL).
- B.** Mine water available in mine voids and from mine discharge in Central Coalfields Limited (CCL), Bharat Coking Coal Limited (BCCL) and Eastern Coalfields Limited (ECL), subsidiaries of CIL, are presently supplied to several colonies of these subsidiary companies of CIL. At some places mine water is drawn by Department of Drinking Water & Sanitation and other agencies/ organizations of Government of Jharkhand. Surplus mine water available at other mines can be used by surrounding habitations for their various needs.
- C.** Presently, about 25250 million gallon of water is estimated to be available in 88 opencast mine voids of CCL, and about 31million gallon/ day of water is estimated to be available as surplus/excess mine water discharge at 23 mine sites of BCCL and 07mine sites of ECL in State of Jharkhand . The list of mines where water is available in mine voids in CCL and in mine water discharge in BCCL and ECL are enclosed at **Annexure I, Annexure II, and Annexure III respectively.**

D. The Parties hereby agree, undertake and affirm as under:-

- i. That sampling and analysis of quality of water available at various mine sites (voids or mine discharge), to assess the suitability for potability, agricultural or other uses will be done by a third party having a recognized environmental laboratory and the party will be selected by mutual consent between CIL (represented by its subsidiaries - CCL, BCCL and ECL) and GoJ.
- ii. The report of analysis of quality of water of various mine sites will be submitted by the selected third party to GoJ and CIL (represented by its subsidiaries - CCL, BCCL and ECL).
- iii. That cost of sampling and analysis of quality of water of various mine sites will be borne by CIL (represented by its subsidiaries - CCL, BCCL and ECL).
- iv. That CIL (represented by its subsidiaries CCL, BCCL and ECL) shall bear all initial cost for construction of civil works like foundation, platform and shed for installation of motor and pumps for drawal of water at identified mine sites.
- v. That Government of Jharkhand shall bear the cost of pumps, motors, associated power supply, pipelines and their installation at identified mine sites from where water is to be drawn. The cost of running these facilities would be borne by Government of Jharkhand or community benefitted.
- vi. The construction, operation and maintenance cost for treatment and distribution facilities of water from identified mine sites will be borne by GoJ.

- vii. The list of mine sites where water is available in voids or as mine discharge are placed at **Annexure I, Annexure II, and Annexure III** for **CCL, BCCL, and ECL** respectively. The number of mine sites may increase / decrease in future. So modalities for pumping water from the additional sites will be same as laid down at serial no D (i) to D (vi).
- viii. In case of dispute, the matter shall be mutually resolved and either party will not be held responsible for non discharge of responsibility under this agreement.
- ix. In case of force majeure or an Act of God, preventing the parties from fulfilling part or all the obligations, both parties shall be exonerated from carrying out further action as per MoU until the force majeure no longer exists.
- x. The MoU will be in force for 30 (thirty) years. The MoU may be renewed as mutually agreed upon by CIL (represented by its subsidiaries CCL, BCCL and ECL) and GoJ beyond the mentioned period of MoU.

Provided further that in case dewatering is required to start coal production in national interest from these mines then the parties will sit together and mutually decide modalities for the same.

- xi. The sustainability of mine sites in respect of future availability of water will be assessed/ studied by CIL.
- xii. This MoU shall be in accordance with applicable Acts, Rules and Guidelines for coal mining including mine closure guidelines and shall not be in contravention with provisions made therein.

IN WITNESS THEREOF, both parties hereto have signed this MoU
in two original copies in English on the date indicated above.

For Coal India Limited

For Government of Jharkhand

Department of Industries, Mines &
Geology

1. Siddh Nath Singh, General
Manager, CSR,
Coal India Limited

1. Aboobacker Siddique P., I.A.S.
Mines Commissioner,
Mines & Geology Department,
Government of Jharkhand.

(.....)

(.....)

Drinking Water & Sanitation
Department

2. Ramesh Kumar,
Engineer in Chief,
Drinking Water & Sanitation
Department, Government of
Jharkhand.

(.....)

Witness 1

(Soumitra Singh)


Witness 1


30/10/16
(Ajay Nath Singh)

Witness 2


Witness 2

Annexure IV

  CENTRAL MINE PLANNING AND DESIGN INSTITUTE LIMITED Environment Laboratory, Regional Institute-II MINE EFFLUENT TEST REPORT		CMPDIL, RI-II KOYLA BHAWAN COMPLEX DHANBAD. -826005 Phone:0326-223-850 email: rdri2cmpdi@coalindia.in	
Test Report for Mine Effluent samples			
Month & Year	04/2022	Cluster	Cluster VII
Customer	Environment Department, Bharat Coking Coal Limited (BCCL), Koyla Bhawan, Dhanbad (E-mail: gmenv.bccl@coalindia.in)		Report No.
Project	Sampling Ref. No.	REM/BCCL/2022/04	Sampling Method
Sampling Stations	(i)	Dhansar OCP	IS 3025 (Part-1) CMPDI/RI-II/LPM 13
Sl. No.	Parameter	Method of Analysis	Period of Analysis
1	Total Suspended Solids	IS 3025/17:1984, R:2017, Gravimetric	APRIL TO MAY 2022
2	pH	IS-3025/11:1983, R-2017, Electrometric	
3	Oil & Grease	IS 3025/39:1991, R:2019, Partition Gravimetric	
4	COD	APHA 23rd Edition 5220 C Titrimetric Method	
Date of Sampling: 11.04.2022 to 25.04.2022 Observed Values: First Fortnight: 28, Second Fortnight: 26 STANDARDS FOR COAL MINES (Stipulated by Ministry of Environment and Forests (MoEF), Vide Notification No. GSR 742(E), Dt: 25.09.2000) LDL: 100 (Max), 5.5 - 9.0, 10 (Max), 250 (Max)			
**All units in mg/L unless specified otherwise. *LDL indicates Lower Detection Limit & BDL indicates Below Detection Limit. **Grab sampling carried out for water samples.			
 ANALYSED BY		 CHECKED BY	
Note: The results above relate to the samples tested as received. This report can not be reproduced in part or full without the written permission of the HOD(Env), CMPDI, RI-II. ---- End of Report ----			
Page -1 of 1			

  CENTRAL MINE PLANNING AND DESIGN INSTITUTE LIMITED Environment Laboratory, Regional Institute-II MINE EFFLUENT TEST REPORT		CMPDIL, RI-II KOYLA BHAWAN COMPLEX DHANBAD. -826005 Phone:0326-223-850 email: rdri2cmpdi@coalindia.in	
Test Report for Mine Effluent samples			
Month & Year	05/2022	Cluster	Cluster VII
Customer	Environment Department, Bharat Coking Coal Limited (BCCL), Koyla Bhawan, Dhanbad (E-mail: gmenv.bccl@coalindia.in)		Report No.
Project	Sampling Ref. No.	REM/BCCL/2022/05	Sampling Method
Sampling Stations	(i)	Dhansar OCP	IS 3025 (Part-1) CMPDI/RI-II/LPM 13
Sl. No.	Parameter	Method of Analysis	Period of Analysis
1	Total Suspended Solids	IS 3025/17:1984, R:2017, Gravimetric	MAY-june 2022
2	pH	IS-3025/11:1983, R-2017, Electrometric	
3	Oil & Grease	IS 3025/39:1991, R:2019, Partition Gravimetric	
4	COD	APHA 23rd Edition 5220 C Titrimetric Method	
Date of Sampling: 09.05.2022 to 23.05.2022 Observed Values: First Fortnight: 61, Second Fortnight: 36 STANDARDS FOR COAL MINES (Stipulated by Ministry of Environment and Forests (MoEF), Vide Notification No. GSR 742(E), Dt: 25.09.2000) LDL: 100 (Max), 5.5 - 9.0, 10 (Max), 250 (Max)			
**All units in mg/L unless specified otherwise. *LDL indicates Lower Detection Limit & BDL indicates Below Detection Limit. **Grab sampling carried out for water samples.			
 ANALYSED BY		 CHECKED BY	
Note: The results above relate to the samples tested as received. This report can not be reproduced in part or full without the written permission of the HOD(Env), CMPDI, RI-II. ---- End of Report ----			
Page -1 of 1			

Annexure V

  cmpdi A Mine Rules Company		CENTRAL MINE PLANNING AND DESIGN INSTITUTE LIMITED Environment Laboratory, Regional Institute-II Ambient Noise Level Test Report				CMPDIL, RI-II KOYLA BHAWAN COMPLEX DHANBAD - 826005 Phone: 0326-223-850 email: rdri2cmpdi@coalindia.in			
Month & Year	04/2022	Cluster	Cluster VII			Report No.	RI-II/NOISE/2022-23/01		
Customer	Environment Department, Bharat Coking Coal Limited (BCCL), Koyla Bhawan, Dhanbad (E-mail: gmenv.bccl@coalindia.in)					Date of Issue	05.07.2022		
Project		Sample Ref. No.	REM/BCCL/2022/04		Sampling Method	CMPDI/RI-II/LPM 13			
Sampling Stations	i	Kusunda OCP		Date of Sampling	08.04.2022	2304.2022	Zone Category of Station:	Core Zone	
Sl. No.	Parameter	Hour / Time of day	Observed Values (in Leq dB(A)) First Fortnight	Observed Values (in Leq dB(A)) Second Fortnight	Method of Analysis	Range Of Testing	LDL	NOISE POLLUTION (REGULATION AND CONTROL) RULES, 2000 Standards	
								Zones	Limits in dB
1	Noise Level dB(A) Leq - Day	06:00 - 07:00	50.3	48.7	CPCB, Protocol for Ambient Level Noise Monitoring - 2015	35 dB-135 dB	35 dB(A)	Industrial Commercial Residential Silence	75 65 55 50
2		07:00 - 08:00	53.0	51.3					
3		08:00 - 09:00	56.4	53.7					
4		09:00 - 10:00	61.7	59.7					
5		10:00 - 11:00	63.1	61.2					
6		11:00 - 12:00	61.7	59.7					
7		12:00 - 13:00	64.6	62.5					
8		13:00 - 14:00	64.9	63.4					
9		14:00 - 15:00	60.2	64.2					
10		15:00 - 16:00	66.0	57.3					
11		16:00 - 17:00	58.7	56.8					
12		17:00 - 18:00	58.2	56.3					
13		18:00 - 19:00	59.2	54.2					
14		19:00 - 20:00	56.3	54.4					
15		20:00 - 21:00	56.3	51.9					
16		21:00 - 22:00	55.1	50.7					
		Leq DAY	61.0	58.9					
1	Noise Level dB(A) Leq - Night	22:00-23:00	47.4	45.8	CPCB, Protocol for Ambient Level Noise Monitoring - 2015	35 dB-135 dB	35 dB(A)	Industrial Commercial Residential Silence	70 55 45 50
2		23:00-00:00	46.7	44.3					
3		00:00-01:00	46.0	44.5					
4		01:00-02:00	45.7	44.2					
5		02:00-03:00	45.2	43.7					
6		03:00-04:00	43.9	42.9					
7		04:00-05:00	44.0	42.6					
8		05:00-06:00	43.6	42.1					
		Leq NIGHT	45.5	43.9					
<i>*LDL indicates Lower Detection Limit</i> <i>**All noise measurements are integrated for a 01 hour period, All units in dB(A)</i>									
 (Gaurav Kant)  (Amit Raj Mishra)									
Sampling Assistants ANALYSED BY		CHECKED BY			HOD's Signature				
Note: The results above relate to the samples tested as received. This report can not be reproduced in part or full without the written permission of the HOD(Env), CMPDI, RI-II.									
--- End of Report --- Page - 1 of 1									



CENTRAL MINE PLANNING AND DESIGN INSTITUTE LIMITED
Environment Laboratory, Regional Institute-II
Ambient Noise Level Test Report

CMPDI, RI-II
 KOYLA BHAWAN COMPLEX
 DHANBAD - 826005
 Phone: 0326-223-850
 email: rdri2cmpdi@coalindia.in

Month & Year	08/2022	Cluster	Cluster VII			Report No.	RI-II/NOISE/2022-23/05	
Customer	Environment Department, Bharat Coking Coal Limited (BCCL), Koyla Bhawan, Dhanbad (E-mail: gmenv.bccl@coalindia.in)					Date of Issue	26.10.2022	
Project		Sample Ref. No.	REM/BCCL/2022/08		Sampling Method	CMPDI/RI-II/LPM 13		
Sampling Stations	i	Kusunda OCP		Date of Sampling	1.08.22	26.08.22	Zone Category of Station:	Core Zone
Sl. No.	Parameter	Hour / Time of day	Observed Values (in Leq dB(A))	Observed Values (in Leq dB(A))	Method of Analysis	Range Of Testing	LDL	NOISE POLLUTION (REGULATION AND CONTROL) RULES, 2000 Standards
			First Fortnight	Second Fortnight				Zones
1	Noise Level dB(A)Leq - Day	06:00 - 07:00	51.5	50.3	CPCB, Protocol for Ambient Level Noise Monitoring - 2015	35 dB-135 dB	35 dB(A)	Industrial Commercial Residential Silence
2		07:00 - 08:00	54.2	53.0				
3		08:00 - 09:00	56.8	55.5				
4		09:00 - 10:00	62.3	61.7				
5		10:00 - 11:00	64.5	63.1				
6		11:00 - 12:00	63.0	61.7				
7		12:00 - 13:00	66.1	64.6				
8		13:00 - 14:00	67.5	65.2				
9		14:00 - 15:00	67.5	60.2				
10		15:00 - 16:00	60.5	59.2				
11		16:00 - 17:00	60.0	67.2				
12		17:00 - 18:00	59.5	58.2				
13		18:00 - 19:00	58.6	57.3				
14		19:00 - 20:00	58.1	56.3				
15		20:00 - 21:00	57.5	55.6				
16		21:00 - 22:00	57.0	55.7				
		Leq DAY	62.5	61.3				
1	Noise Level dB(A)Leq - Night	22:00-23:00	44.5	45.9	CPCB, Protocol for Ambient Level Noise Monitoring - 2015	35 dB-135 dB	35 dB(A)	Industrial Commercial Residential Silence
2		23:00- 00:00	43.8	44.5				
3		00:00- 01:00	43.6	43.0				
4		01:00-02:00	43.1	41.5				
5		02:00-03:00	41.2	42.0				
6		03:00-04:00	40.8	40.8				
7		04:00-05:00	39.8	39.4				
8		05:00-06:00	39.5	39.0				
		Leq NIGHT	42.4	42.6				

*LDL indicates Lower Detection Limit
 **All noise measurements are integrated for a 01 hour period. All units in dB(A)

Sampling Assistants	 (Gaurav Kant)	 (Amit Raj Mishra)
ANALYSED BY	CHECKED BY	HOD's Signature

Note: The results above relate to the samples tested as received. This report can not be reproduced in part or full without the written permission of the HOD(Env), CMPDI, RI-II.

--- End of Report ---
 Page -1 of 1

Annexure VI**Status of Periodical Medical Examination**

Sl. No.	Name of Area/ Mine/ Office	October	November	December	January	February	March
1	ADIC	60	68	35	15	0	0
2	ENA	4	1	2	3	0	0
3	Kusunda	40	45	74	33	0	0
4	Burragarh	3	2	2	3	0	0
4	Hurrladih	2	1	4	2	0	0
5	Kustore Colliery	1	2	1	1	0	0
6	Rajapur/S-Jharia	20	21	7	0	0	0
7	AEBSC	7	5	11	0	0	0
Total		137	145	136	57	0	0

Annexure VII**Status of Training**

Sl. No.	Month	Refresher Training	Initial Training	Contractual Worker	Change of Job	Special Training
1	April	26	1	0	0	0
2	May	32	0	0	0	27
3	June	36	0	8	3	13
4	July	33	3	0	0	15
5	August	49	0	10	0	0
6	September	39	3	8	0	42
Total		215	7	26	3	97

Ref No- BCCL/KA/ED/2022/178

To
The General Manager (Estate)
Koyla Bhawan
Sub- Submission of Monthly Report

Date-09/11/22

Sub- Submission of Monthly Report												
Status of unauthorised Encroachment on Coal Bearing Area in Kusunda Area , BCCL AS ON 09.11.2022										Possession taken		
Area	NO. Of Encroachers			No of Case Filed			No of order Passed			Possession taken		
	Quarter	Land	Total	Quarter	Land	Total	Quarter	Land	Total	Quarter	Land	Total
KUSUNDA	892	1290	2182	892	1290	2182	544	474	1018	700	140	840
Status of unauthorised Encroachment on Non Coal Bearing Area in Kusunda Area, BCCL AS ON 03.08.2022												
Area	NO. Of Encroachers			No of Case Filed			No of order Passed			Possession taken		
	Quarter	Land	Total	Quarter	Land	Total	Quarter	Land	Total	Quarter	Land	Total
KUSUNDA	327	192	519	327	192	519	317	57	374	107	0	107
Status of transfer of Title of Agreemental Land as on 03.09.2022												
Area	No. of Employment given	Under CNT Act	CNT Free	Total	Files Given to Advocate (for CNT Cases)	Case Filed (CNT)	Order Passed	Schedule for Filling rest cases	Remarks	Status		
KUSUNDA	10	5	1	6	5	5	2 Under CNT	Nil	Four No. of the submitted to HQ for approval, no decision has been taken by HQ as the land is Vested Land			

Addl. General Manager
Kusunda Area

Area Manager (Estate)
Kusunda Area

C.C. to : The General Manager, Kusunda Area
The AM (Personnel/Admin), Kusunda Area



COAL INDIA LIMITED



CORPORATE ENVIRONMENT POLICY

2018

Environmental Policy Statement:

Coal India Limited(CIL) is committed to promote sustainable development by protecting the environment through integrated project planning & design, prevention/mitigation of pollution, conservation of natural resources, restoration of ecology & biodiversity, recycling/ proper disposal of wastes, addressing climate change and inclusive growth. It also aims to bringing awareness amongst its stakeholders for continual improvement in environmental performances following best practices.

OBJECTIVES:

Coal India Limited shall endeavor to:

- 1. Plan & design projects with due consideration to environmental concerns for Sustainable Development.*
- 2. Conduct mining and associated operation in an environmentally responsible manner to comply with applicable laws and other requirements related to environmental aspects.*
- 3. Prevent pollution of surrounding habitation by continuous monitoring and adopting suitable measures for environment protection.*
- 4. Implement Environment Management Plans in all our mines /projects effectively to mitigate pollution, conservation of natural resources and restoration of ecology & biodiversity.*
- 5. Ensure compliance of all applicable Environmental Clearance& Forestry Clearance conditions and other statutory conditions issued by regulatory agencies.*
- 6. Recycling of wastes on the principle of REDUCE, REUSE and RECYCLE.*
- 7. Put special thrusts on efficient energy utilization / renewable energy as a measure to reduce carbon foot-print.*
- 8. Strive for continual improvement in our environmental performances by setting targets, measuring progress and taking corrective action.*
- 9. Taking measures to render productive post mining land use.*
- 10.Implementation of activities applicable to CIL arising out of International Conventions.*
- 11.Create environmental awareness among the employees and the local communities through pro-active communication and training.*

STRATEGIES FOR IMPLEMENTATION OF ENVIRONMENTAL POLICY:

Back Ground:

Coal India Limited subscribes to the view of Sustainable Development. Unless the environment can sustain all the developmental activities, any pursuit of development in isolation can cause irreparable damage to the ecosystem and associated environmental attributes. Keeping this view in mind, Coal India Limited attaches top priority towards sustainable development and approved its 'Corporate Environmental Policy' in December 1995, which was subsequently revised in 2012. However the present policy is the amendment of the 2012 Policy and is complimentary to the National Environmental Policy, 2006.

This modification in the present policy is the outcome of the experience gained since 2012 keeping in view the modifications / amendments made time to time in environmental policies and additional stipulation notified by MoEF&CC (Ministry of Environment, Forest& Climate Change) and other organisations concerning mine closure, reclamation of degraded land, environmental clearance etc. and also with the objective of revisiting the corporate policy.

This Policy has a vision of Green Mining and mission of 100% compliance of environmental statutes applicable to coal mining industry.

Strategies: Coal India adopts the strategies appended below for effective implementation:

1.MINE/ PROJECT PLANNING & DESIGN FOR SUSTAINABLE DEVELOPMENT:

- a) Coal being a non-renewal energy source, extraction shall be planned prudently to meet national requirement in a planned way. The projects shall be designed on the principle of Sustainable Development with due consideration to environment, mine closure, safety and aspirations of the stakeholders at the planning& design stage itself with due regard to mine closer plan.
- b) While preparing the Mining plan/project reports, the effort shall be to incorporate latest mining technologies and equipment's with optimal capacity, which are more environment friendly.

- c) All Mining Plan/ project reports will be provided with detailed provisions for ensuring environmental compliances.

2. ENVIRONMENTAL IMPACT ASSESSMENT (EIA) & ENVIRONMENT MANAGEMENT PLAN (EMP)

- a. All mine planning and design shall be environmentally acceptable and operation shall be carried out in such a way as to facilitate the compliance of stipulated environmental standards.
- b. EIA& EMP for all projects shall be formulated as per the approved ToR (Terms of Reference) and public consultations for obtaining Environmental Clearance (EC) from MoEF&CC. Similarly, in the existing projects needing enhancement of production capacities with or without increase in land, change of technology, renewal of lease and change in land use etc. fresh EC is required to be sought as per norms. The projects shall be operated after obtaining Consent to Establish (CTE)/Consent to Operate (CTO) from State Pollution Control Boards (SPCB).
- c. Detailed Mine Closure Plans shall be prepared for all existing and new mines as per the MoC (Ministry of Coal) guidelines.

3. COMPLIANCE OF THE STATUTORY REQUIREMENTS:

The implementation of EMP and fulfillment of all other statutory requirements like conditions of EC, FC and consents to establish & operate, including timely submission of returns to statutory bodies and various agencies, are to be ensured at all levels.

4. MEASURES TO MITIGATE POLLUTION:

a) Air Pollution:

- i) Generation of dust is to be controlled at the source to the possible extent with necessary control measures during drilling, blasting, loading, unloading, CHP transfer points etc.
- ii) Deployment of eco-friendly mining technologies.
- iii) Dust generation is to be minimized along coal / waste transportation routes.
- iv) Mechanized transportation of coal to be encouraged.
- v) Green belt is to be created around the source of dust.

b) Water pollution:

- i) The mine water and other effluent shall be treated to ensure the discharge norms as per statute. The treated effluent shall be utilized to the extent possible with a view to achieve maximum water conservation.
- ii) Oil & grease from the effluent shall be removed by Oil & Grease Traps for proper disposal.

c) Noise / ground vibration:

- i) All measures to minimize noise pollution will be taken including maintenance of HEMM, equipment and provision of PPE where required.
- ii) Suitable controlled blasting techniques shall be followed to reduce ground vibration as well as noise pollution.

d) Land reclamation:

- i) Progressive and concurrent reclamation of mined out areas will be carried out as per approved EIA/EMP and Mine Closure Plan (MCP).
- ii) Slopes of external dumps are the important area to be suitably graded / terraced for effective reclamation and plantation.
- iii) Preservation of top soil is required for future use. Old as well as existing non- active dumps are to be technically and biologically reclaimed.
- iv) Monitoring of reclamation work of all opencast mines will be done through Satellite Surveillance. The outcome shall be put in the websites.

e) Mine closure plans:

Mine Closure Plan (MCP) shall be prepared for each mine. MCP are being delineated in two phases viz. progressive and final mine closure. Appropriate funds are set aside and deposited under a special Escrow fund every year as per MoC guidelines, to be utilized for proper and final mine closure.

For mines closed prior to issuance of MoC guidelines (i.e. 27th August, 2009) suitable action to be taken as per provisions of Mines Act 1952.

f) Mine fire

CIL shall endeavour to reduce occurrence of mine fire and subsidence due to mining activity. Monthly report shall be submitted to top management of the subsidiary and CIL and Quarterly to company board. Action Plan for mine fire control shall be implemented. Monitoring will be done through Satellite Surveillance/other suitable technology.

g) Monitoring:

- I. All receptors in and around the mining projects shall be monitored regularly to assess the efficacy of the pollution control / mitigation measures within stipulated standards.
- II. Effect of mining on the hydrology of the area will be monitored through measurement of water level and its quality of nearby wells and bore holes provided for this purpose. Conservation of water through rainwater harvesting shall be taken up.
- III. Area and Unit environmental cells shall have regular interaction with the people in and around the coal mines and other allied units on matters related to environment to take necessary and timely corrective actions.
- V. Environmental initiatives and monitoring through self and third party environment audit shall be conducted for generating useful data for taking corrective actions and mitigation measures as per guidelines.

h) Other measures:

- I. Special emphasis shall be given to undertake R&D related to various facets of coal mine environmental management in collaboration with Central Mine Planning and Design Institute (CMPDI) and other competent institutions.
- II. Besides ensuring statutory compliance, the CIL desires to set high standards and continual improvement.
- III. A number of mines and establishments of CIL are ISO 14001 certified and balance mines & establishments shall be ISO 14001 certified in phased manner.
- IV. CSR and R&R policies of CIL are to be incorporated for better planning and implementation of the socio-economic issues of coal mining areas.
- V. The coal mining environmental issues are complex and require multi-disciplinary approach to address the same. CIL will endeavor to enter into MoUs with expert agencies of repute to assist in environment issues and also help in capacity building of CIL executives.
- VI. CIL conduct periodical medical examination (PME) of its work force on routine basis in compliance of the requirement mining rules and regulation, additional test will be done as and when require.

5. PRESERVATION OF BIO-DIVERSITY:

- a) This will start from mine planning including technically and biologically reclamation of mined out areas in collaboration with State Forest Departments, Wild Life Divisions, NGOs etc. working in the fields of bio- diversity conservation.

- b) The selection of species for plantation shall be done in consultation with the local community to include the local species and their preferences, if any.

6. COAL BENEFICIATION / COALWASHERIES:

- a) For beneficiation of Runoff Mines (ROM) coal, washeries are being set up in a phased manner as per requirement and statutes.
- b) Slurry Management System (SMS) in all washeries shall be organized to ensure collection of fines, gainful utilization of rejects viz. power generation in Fluidized Bed Combustion (FBC) plants, selling to brick manufacturers or adopting other environmental friendly disposal options as feasible.
- c) The reject dumps and tailings shall be suitably handled to avoid any contamination.
- d) The effluent from washeries including tailings pond shall be suitably treated and reused to minimize water consumption with zero discharge concept.

7. CONSERVATION AND CLEAN TECHNOLOGY:

- a) R&D projects shall be taken up to promote clean coal technology and improve the existing technologies.
- b) Energy saved is energy produced. Voluntary energy audit to be done for corrective action to reduce carbon footprint.
- c) Clean Development Mechanisms will be explored for reducing emission of Green House Gases by exploration, identification, preparation of projects reports for extraction of methane from Coal Bed, Coal Mine, Abandoned Mine, Ventilation Air, UG Coal Gasification, generation and utilization of renewable energy etc.

8. AWARENESS PROGRAMME:

- a) Publicity to generate awareness through exchange & communication of information, newsletters and periodicals on environment, seminars, work- shops, celebration of World Environment Day etc. at CIL / Subsidiary HQs, Areas & units to be undertaken. Regular training programs to be organized at various levels to inculcate awareness among employees.
- b) Courses on environmental and forestry laws and Environmental

Protection Measures and the Corporate Policy to be organized for project executives for improving knowledge.

- c) CIL to give annual awards for achieving excellence in environment related

issues and activities. These awards will be in recognition for implementation of EMP, land reclamation and compliance of statutes, proper maintenance of air & water quality and noise level.

9. WASTE MANAGEMENT:

CIL will undertake appropriate action for safe handling, storage and disposal of solid waste and hazardous waste generated from its industrial set up and colonies as per relevant rules. The biomedical waste generated from hospitals and dispensaries will be collected and disposed in appropriate facilities created as per statutes. E-waste management and handling of various types of e-waste generated in its operations will be done as per rule.

10. CORPORATE ENVIRONMENT RESPONSIBILITY:

Corporate Environment Responsibility (CER) is mandatory for issuing environmental clearance for all the Greenfield and Brownfield projects as per directives of MoEFCC with effect from 1st May, 2018 (O.M.No.22-65/2017- IAIII dt. 19.06.2018). Budgetary provisions should be kept for implementation of provisions of CER for all the projects which will be submitted to MoEFCC for grant of environmental clearance.

11. INCORPORATION OF VIEWS OF STAKEHOLDERS:

CIL will critically examine and incorporate the viewpoints of various stakeholders like PAPs/PAFs, Parliamentary Committees, Standing Sub-Committees, NGOs etc. CIL being a listed entity with stock exchange, it will also take into consideration the observations/viewpoints of international investors.

12. IMPLEMENTATION OF POLICY:

- i) **Manpower:** CIL shall have environmental divisions at decision making & operational levels in its structure. The environment department shall be set up and strengthened at:
- i) CIL Corporate HQ at Kolkata
 - ii) Subsidiary HQs
 - iii) Areas / Units / Collieries / Workshops / Washeries
 - iv) CMPDI (HQ) & CMPDI Regional Institutes

- ii) **Roles and Responsibilities:** The environmental department, set up at company HQs, Areas and Unit levels with appropriate manpower and resources, shall be responsible for implementation of policy, obtaining EC, FC, consent to establish

& operate, statutes requirements and undertaking mitigation measures besides preparation of action plan every year and also to intimate the status of implementation to the management regularly.

- iii) **Annual Environment Budget (Revenue &Capital):** The Annual Environment Budget (revenue & capital) shall be prepared based on the action plan including monitoring of various bench marks and the budget utilization. The year wise funds earmarked for environmental protection measures shall be kept in separate accounts with Environmental cost code.

13. FLEXIBILITY TO THE SUBSIDIARY COMPANIES:

CEP 2018 will be applicable for all subsidiaries of CIL. The subsidiary company Boards have been authorized to approve necessary modifications in CEP 2018 with reference to unique conditions prevailing at the concerned subsidiary.

REVIEW OF ENVIRONMENTAL POLICY:

In view of the present fast changing social, economic and environmental scenario, this Policy shall be reviewed every 5 years to incorporate the changes in the legal, technical, environmental, economic and social inputs prevailing at that time. Whenever, there is change in National Environmental Policy or other National / State relevant policies, Acts etc, this Corporate Environmental Policy would be reviewed and suitably revised.



झारखण्ड राज्य प्रदूषण नियंत्रण पर्वद्
Jharkhand State Pollution Control Board
HIG-1, Housing Colony, Dhanbad-826001

Ph: 0326-2204933

(7)

Letter No.....2650

Dated6/7/13.....

From,

Regional Officer,
Dhanbad

To,

HOD (Env.),
M/s. B.C.C.L.,
Koyla Bhawan, Koyla Nagar,
Dhanbad.Sub: **Fixing up monitoring station/Sampling location of Air, Water & Noise.**

Sir,

With reference to you letter no. GM(Env.)/F-JSPCB/2013/783, dt. 06.07.2013 We have approved Air, Water & Noise monitoring Station/Sampling location after verification and return a copy of the map.

Encl-A/a.

Your's faithfully,

6/7/13
(Dinesh Prasad Singh)
Regional Officer.

Memo.....

Dhanbad, dated.....

Copy to: The Member Secretary, Jharkhand State Pollution Control Board for information & enclose a copy of the map for necessary action.

Encl-A/a.

(Dinesh Pd. Singh)
Regional Officer.


The map illustrates the Jharia Coalfield, a large industrial area in Jharkhand, India. It is divided into 10 clusters (I to X) for sampling purposes. The legend indicates that blue dots represent sampling locations of *Torus* (blue), red dots represent *Torus* (red), and green dots represent *Torus* (green). The inset map shows the location of the Jharia Coalfield within the state of Jharkhand, India.

	1973-74	1974-75	1975-76	1976-77	1977-78	1978-79	1979-80	1980-81	1981-82	1982-83	1983-84	1984-85	1985-86	1986-87	1987-88	1988-89	1989-90	1990-91	1991-92	1992-93	1993-94	1994-95	1995-96	1996-97	1997-98	1998-99	1999-00	2000-01	2001-02	2002-03	2003-04	2004-05	2005-06	2006-07	2007-08	2008-09	2009-10	2010-11	2011-12	2012-13	2013-14	2014-15	2015-16	2016-17	2017-18	2018-19	2019-20	2020-21	2021-22	2022-23	2023-24	2024-25	2025-26	2026-27	2027-28	2028-29	2029-30	2030-31	2031-32	2032-33	2033-34	2034-35	2035-36	2036-37	2037-38	2038-39	2039-40	2040-41	2041-42	2042-43	2043-44	2044-45	2045-46	2046-47	2047-48	2048-49	2049-50	2050-51	2051-52	2052-53	2053-54	2054-55	2055-56	2056-57	2057-58	2058-59	2059-60	2060-61	2061-62	2062-63	2063-64	2064-65	2065-66	2066-67	2067-68	2068-69	2069-70	2070-71	2071-72	2072-73	2073-74	2074-75	2075-76	2076-77	2077-78	2078-79	2079-80	2080-81	2081-82	2082-83	2083-84	2084-85	2085-86	2086-87	2087-88	2088-89	2089-90	2090-91	2091-92	2092-93	2093-94	2094-95	2095-96	2096-97	2097-98	2098-99	2099-00	2100-01	2101-02	2102-03	2103-04	2104-05	2105-06	2106-07	2107-08	2108-09	2109-10	2110-11	2111-12	2112-13	2113-14	2114-15	2115-16	2116-17	2117-18	2118-19	2119-20	2120-21	2121-22	2122-23	2123-24	2124-25	2125-26	2126-27	2127-28	2128-29	2129-30	2130-31	2131-32	2132-33	2133-34	2134-35	2135-36	2136-37	2137-38	2138-39	2139-40	2140-41	2141-42	2142-43	2143-44	2144-45	2145-46	2146-47	2147-48	2148-49	2149-50	2150-51	2151-52	2152-53	2153-54	2154-55	2155-56	2156-57	2157-58	2158-59	2159-60	2160-61	2161-62	2162-63	2163-64	2164-65	2165-66	2166-67	2167-68	2168-69	2169-70	2170-71	2171-72	2172-73	2173-74	2174-75	2175-76	2176-77	2177-78	2178-79	2179-80	2180-81	2181-82	2182-83	2183-84	2184-85	2185-86	2186-87	2187-88	2188-89	2189-90	2190-91	2191-92	2192-93	2193-94	2194-95	2195-96	2196-97	2197-98	2198-99	2199-00	2200-01	2201-02	2202-03	2203-04	2204-05	2205-06	2206-07	2207-08	2208-09	2209-10	2210-11	2211-12	2212-13	2213-14	2214-15	2215-16	2216-17	2217-18	2218-19	2219-20	2220-21	2221-22	2222-23	2223-24	2224-25	2225-26	2226-27	2227-28	2228-29	2229-30	2230-31	2231-32	2232-33	2233-34	2234-35	2235-36	2236-37	2237-38	2238-39	2239-40	2240-41	2241-42	2242-43	2243-44	2244-45	2245-46	2246-47	2247-48	2248-49	2249-50	2250-51	2251-52	2252-53	2253-54	2254-55	2255-56	2256-57	2257-58	2258-59	2259-60	2260-61	2261-62	2262-63	2263-64	2264-65	2265-66	2266-67	2267-68	2268-69	2269-70	2270-71	2271-72	2272-73	2273-74	2274-75	2275-76	2276-77	2277-78	2278-79	2279-80	2280-81	2281-82	2282-83	2283-84	2284-85	2285-86	2286-87	2287-88	2288-89	2289-90	2290-91	2291-92	2292-93	2293-94	2294-95	2295-96	2296-97	2297-98	2298-99	2299-00	2300-01	2301-02	2302-03	2303-04	2304-05	2305-06	2306-07	2307-08	2308-09	2309-10	2310-11	2311-12	2312-13
1	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312								



 Sampling location at various sites (openness/ accessibility)
 Sampling location at this value
 Sampling location at this value
 Sampling location at lowest/ highest value

NAME	BEIJING COINING COAL LIMITED
NO.	SHANGHAI SHANGHAI COINING
CODE	SHANGHAI SHANGHAI COINING
CHINA	SHANGHAI SHANGHAI COINING



Location of Air & Noise Monitoring Stations in BCCL





AMBIENT AIR QUALITY DATA

  		CENTRAL MINE PLANNING AND DESIGN INSTITUTE LIMITED Environment Laboratory, Regional Institute-II Ambient Air Quality Test Report		CMPDIL, RI-II KOYLA BHAWAN COMPLEX DHANBAD, -826005 Phone: 0326-223-850 email: rdri2cmpdi@coalindia.in	
Test Report for Ambient Air Samples					
Month & Year	04/2022		Cluster	Cluster VII	
Customer	Environment Department, Bharat Coking Coal Limited (BCCL), Koyla Bhawan, Dhanbad (E-mail: gmenv.bccl@coalindia.in)			Report No.	RI-II/AIR/2022-23/01
Project	Sample Ref. No.		REM/BCCL/2022/04	Sampling Method	CMPDI/RI-II/LPM 13, (IS 5182)
Sampling Stations	i	Kusunda OCP	Date of Sampling	07.04.2022	22.04.2022
Zone of Station:	Core Zone				
Sl. No.	Parameter	Method Analysis of	Observed Values (in $\mu\text{g}/\text{m}^3$)	Range Of Testing	LDL
			1st FN	2nd FN	
1	PM ₁₀	IS -5182(Part 23):2006, R-2017	134	132	10 $\mu\text{g}/\text{m}^3$ - 1000 $\mu\text{g}/\text{m}^3$
2	PM _{2.5}	IS -5182(Part 24):2019	77	74	10 $\mu\text{g}/\text{m}^3$ - 400 $\mu\text{g}/\text{m}^3$
3	SO ₂	IS-5182(Part-2): 2001, R-2017	10	<10	10 $\mu\text{g}/\text{m}^3$ - 1050 $\mu\text{g}/\text{m}^3$
4	NO ₂	IS-5182 (Part-6): 2006, R-2017	32	30	06 $\mu\text{g}/\text{m}^3$ - 420 $\mu\text{g}/\text{m}^3$
**All units are in $\mu\text{g}/\text{m}^3$, 24 hourly Average * LDL indicates Lower Detection Limit,					
 ANALYSED BY		 (Gaurav Kant) CHECKED BY		 (Amit Raj Mishra) HOD's Signature	
Note: The results above relate to the samples tested as received. This report can not be reproduced in part or full without the written permission of the HOD(Env), CMPDI, RI-II.					
--- End of Report ---					
Page -1 of 1					


AMBIENT AIR QUALITY DATA

  		CENTRAL MINE PLANNING AND DESIGN INSTITUTE LIMITED Environment Laboratory, Regional Institute-II Ambient Air Quality Test Report		CMPDIL, RI-II KOYLA BHAWAN COMPLEX DHANBAD, -826005 Phone: 0326-223-850 email: rdri2cmpdi@coalindia.in	
Test Report for Ambient Air Samples					
Month & Year	05/2022		Cluster	Cluster VII	
Customer	Environment Department, Bharat Coking Coal Limited (BCCL), Koyla Bhawan, Dhanbad (E-mail: gmenv.bccl@coalindia.in)			Date of Issue	10.08.2022
Project	Sample Ref. No.		REM/BCCL/2022/05	Sampling Method	CMPDI/RI-II/LPM 13, (IS 5182)
Sampling Stations	i	Kusunda OCP	Date of Sampling	10.05.22	24.05.22
Zone of Station:	Core Zone				
Sl. No.	Parameter	Method Analysis of	Observed Values (in $\mu\text{g}/\text{m}^3$)	Range Of Testing	LDL
			1st FN	2nd FN	
1	PM ₁₀	IS -5182(Part 23):2006, R-2017	130	128	10 $\mu\text{g}/\text{m}^3$ - 1000 $\mu\text{g}/\text{m}^3$
2	PM _{2.5}	IS -5182(Part 24):2019	69	71	10 $\mu\text{g}/\text{m}^3$ - 400 $\mu\text{g}/\text{m}^3$
3	SO ₂	IS-5182(Part-2): 2001, R-2017	10	10	10 $\mu\text{g}/\text{m}^3$ - 1050 $\mu\text{g}/\text{m}^3$
4	NO ₂	IS-5182 (Part-6): 2006, R-2017	30	33	06 $\mu\text{g}/\text{m}^3$ - 420 $\mu\text{g}/\text{m}^3$
**All units are in $\mu\text{g}/\text{m}^3$, 24 hourly Average * LDL indicates Lower Detection Limit,					
 ANALYSED BY		 (Gaurav Kant) CHECKED BY		 (Amit Raj Mishra) HOD's Signature	
Note: The results above relate to the samples tested as received. This report can not be reproduced in part or full without the written permission of the HOD(Env), CMPDI, RI-II.					
--- End of Report ---					
Page -1 of 1					



AMBIENT AIR QUALITY DATA

  		CENTRAL MINE PLANNING AND DESIGN INSTITUTE LIMITED Environment Laboratory, Regional Institute-II Ambient Air Quality Test Report		CMPDIL, RI-II KOYLA BHAWAN COMPLEX DHANBAD. - 826005 Phone: 0326-223-850 email: rdri2cmpdi@coalindia.in				
Test Report for Ambient Air Samples								
Month & Year	06/2022	Cluster	Cluster VII	Report No.	RI-II/AIR/2022-23/03			
Customer	Environment Department, Bharat Coking Coal Limited (BCCL), Koyla Bhawan, Dhanbad (E-mail: gmenv.bccl@coalindia.in)			Date of Issue	07.09.2022			
Project		Sample Ref. No.	REM/BCCL/2022/06	Sampling Method	CMPDI/RI-II/LPM 13, (IS 5182)			
Sampling Stations	i	Kusunda OCP	Date of Sampling	01.06.22	17.06.22			
Sl. No.	Parameter	Method Analysis of	Observed Values (in $\mu\text{g}/\text{m}^3$)		Range Of Testing	LDL	MoEF Standards Notification dated 25th September, 2000 (GSR 742 E)	NAAQS, 2009
			1st FN	2nd FN				
1	PM ₁₀	IS -5182(Part 23):2006, R-2017	98	95	10 $\mu\text{g}/\text{m}^3$ - 1000 $\mu\text{g}/\text{m}^3$	10 $\mu\text{g}/\text{m}^3$	300	100
2	PM _{2.5}	IS -5182(Part 24):2019	59	55	10 $\mu\text{g}/\text{m}^3$ - 400 $\mu\text{g}/\text{m}^3$	10 $\mu\text{g}/\text{m}^3$	Not Specified	60
3	SO ₂	IS-5182(Part-2): 2001, R-2017	<10	<10	10 $\mu\text{g}/\text{m}^3$ - 1050 $\mu\text{g}/\text{m}^3$	10 $\mu\text{g}/\text{m}^3$	120	80
4	NO ₂	IS-5182 (Part-6): 2006, R-2017	26	23	06 $\mu\text{g}/\text{m}^3$ - 420 $\mu\text{g}/\text{m}^3$	06 $\mu\text{g}/\text{m}^3$	120	80
**All units are in $\mu\text{g}/\text{m}^3$, 24 hourly Average * LDL indicates Lower Detection Limit,								
 ANALYSED BY			 CHECKED BY			 HOD's Signature		
Note: The results above relate to the samples tested as received. This report can not be reproduced in part or full without the written permission of the HOD(Env), CMPDI, RI-II.								
---- End of Report ---- Page -1 of 1								

AMBIENT AIR QUALITY DATA

  		CENTRAL MINE PLANNING AND DESIGN INSTITUTE LIMITED Environment Laboratory, Regional Institute-II Ambient Air Quality Test Report		CMPDIL, RI-II KOYLA BHAWAN COMPLEX DHANBAD. - 826005 Phone: 0326-223-850 email: rdri2cmpdi@coalindia.in				
Test Report for Ambient Air Samples								
Month & Year	08/2022	Cluster	Cluster VII	Report No.	RI-II/AIR/2022-23/05			
Customer	Environment Department, Bharat Coking Coal Limited (BCCL), Koyla Bhawan, Dhanbad (E-mail: gmenv.bccl@coalindia.in)			Date of Issue	26.10.2022			
Project		Sample Ref. No.	REM/BCCL/2022/08	Sampling Method	CMPDI/RI-II/LPM 13, (IS 5182)			
Sampling Stations	i	Kusunda OCP	Date of Sampling	01.08.2022	26.08.2022			
Sl. No.	Parameter	Method Analysis of	Observed Values (in $\mu\text{g}/\text{m}^3$)		Range Of Testing	LDL	MoEF Standards Notification dated 25th September, 2000 (GSR 742 E)	NAAQS, 2009
			1st FN	2nd FN				
1	PM ₁₀	IS -5182(Part 23):2006, R-2017	96	92	10 $\mu\text{g}/\text{m}^3$ - 1000 $\mu\text{g}/\text{m}^3$	10 $\mu\text{g}/\text{m}^3$	300	100
2	PM _{2.5}	IS -5182(Part 24):2019	52	48	10 $\mu\text{g}/\text{m}^3$ - 400 $\mu\text{g}/\text{m}^3$	10 $\mu\text{g}/\text{m}^3$	Not Specified	60
3	SO ₂	IS-5182(Part-2): 2001, R-2017	11	<10	10 $\mu\text{g}/\text{m}^3$ - 1050 $\mu\text{g}/\text{m}^3$	10 $\mu\text{g}/\text{m}^3$	120	80
4	NO ₂	IS-5182 (Part-6): 2006, R-2017	25	26	06 $\mu\text{g}/\text{m}^3$ - 420 $\mu\text{g}/\text{m}^3$	06 $\mu\text{g}/\text{m}^3$	120	80
**All units are in $\mu\text{g}/\text{m}^3$, 24 hourly Average * LDL indicates Lower Detection Limit,								
 ANALYSED BY			 CHECKED BY			 HOD's Signature		
Note: The results above relate to the samples tested as received. This report can not be reproduced in part or full without the written permission of the HOD(Env), CMPDI, RI-II.								
---- End of Report ---- Page -1 of 1								

Annexure XII

  		CENTRAL MINE PLANNING AND DESIGN INSTITUTE LIMITED Environment Laboratory, Regional Institute-II MINE EFFLUENT ANALYSIS TEST REPORT				CMPDIL, RI-II KOYLA BHAWAN COMPLEX DHANBAD. -826005 Phone:0326-223-850 mail: rdri2cmpdi@coalindia.in			
Month & Year	QUARTER ENDING JUNE 2022	Cluster	CLUSTER VII			Report No.	RI-2/MW/2022-23/HY/01		
Customer	Environment Department, Bharat Coking Coal Limited (BCCL), Koyla Bhawan, Dhanbad (E-mail: gmenv.bccl@coalindia.in)					Date of Issue	25.10.2022		
Project	Dhansar Colliery	Sample Ref. No.	REM/BCCL/2022/MW/06/01		Sampling Method	CMPDI/RI-II/LPM 13,(IS 3025:Part -1)			
Sampling Stations	MW7	Date of Sampling	20.06.22		Sample Collected in 5 Ltr Jerricane, Color as observed is transparent				
				Period of Analysis	JUNE	TO	SEPT'2022		
Sl. No.	Parameter	Method of Analysis	MW7	Range Of Testing	LDL	MOEF -SCH-VI STANDARDS Class 'A'			
1	B.O.D (3 days 27°C), mg/l, Max	IS 3025 /44:1993,R:20033 day incubation at 27°C	<1.0	2-1000.0	2	30			
2	Colour	APHA, 23 RD Edition, 2120-B:-2017	4	1.0-500.0	1	-			
3	COD, mg/l, Max	APHA 23rd Edition 5220 C Titrimetric Method	24	4.0-800.0	4	250			
4	Copper (as Cu), mg/l, Max	IS 3025(Part42): 1992 R : 2019, AAS-Flame	<0.2	0.2-10.0	0.2	3			
5	Dissolved Phosphate (as P), mg/l, Max	IS 3025/ 31, 1988 R 2019	<0.1	0.1-5	0.1	5			
6	Fluoride (as F) mg/l, Max	APHA, 23 RD Edition, Page 4-90 to , 4500 -F- D (SPADNS Method)	0.59	0.2-2	0.2	2			
7	Hexavalent Chromium, mg/l, Max	IS 3025 (Part 52) : 2003, Reaffirmed 2019	<0.01	0.01-1.4	0.01	0.1			
8	Iron (as Fe), mg/l, Max	IS 3025 (Part 53) : 2003, R : 2019 , AAS-Flame	<0.2	0.2-10	0.2	3			
9	Manganese(as Mn), mg/l, Max	APHA, 23 rd Edition, AAS-GTA	<0.2	0.1-10	0.005	0.1			
10	Nickel (as Ni), mg/l, Max	IS-3025(Part 54):2003, R:2019 AAS-Flame	<0.2	0.1-10.0	0.1	3			
11	Nitrate Nitrogen, mg/l, Max	APHA, 23 rd Edition, UV-Spectrophotometric	2.04	0.5-45	0.5	10			
12	Oil & Grease, mg/l, Max	IS 3025/39:1991, R : 2019, Partition Gravimetric	<2.0	2.0-1000	2	10			
13	pH value	IS-3025/11:1983, R-2017, Electrometric	8.05	1-14	0.1	5.5 to 9.0			
14	Temperature (°C)	IS-3025/09:1984, Thermometric	33.6	1-100	1	Shall not exceed 5° C above the receiving temp.			
15	Total Chromium (as Cr), mg/l, Max	IS-3025(Part 52):2003, R:2019 AAS-Flame	<0.2	0.1-8	0.1	2			
16	Total Suspended Solids, mg/l, Max	IS 3025/17:1984, R :2017, Gravimetric	39	10-5000	10	100			
17	Zinc (as Zn), mg/l, Max	IS 3025 /49 : 1994, R : 2019, AAS-Flame	<0.2	0.1-2.0	0.1	5			
18	Odour	APHA, 23rd Edition, , 2150-C	Agreeable	Qualitative	Qualitative	Qualitative			
***All units in mg/L unless specified otherwise,									
**Grab sampling carried out for water samples. *LDL indicates Lower Detection Limit & BDL indicates Below Detection Limit,									
 ANALYSED BY			 CHECKED BY			 HOD's Signature			
Note: The results above relate to the samples tested as received. This report can not be reproduced in part or full without the written permission of the HOD(Env) , CMPDI, RI-II.									

	भारत कोकिंग कोल लिमिटेड 'एक मिनीरल्स कम्पनी' (कोल इण्डिया लिमिटेड का एक अंग)	
पर्यावरण विभाग, कोयला भवन		
सभी संबंधित व्यक्तियों को सूचित किया जाता है कि भारत कोकिंग कोल लिमिटेड के क्लस्टर VII कोयला खनन परियोजना को पर्यावरण, वन एवं जलवायु परिवर्तन मंत्रालय के द्वारा पर्यावरणीय स्वीकृति में संशोधन दिया गया है जो इस प्रकार है :-		
क्रम संख्या	परियोजना का नाम	स्वीकृति पत्र संख्या एवं दिनांक
1.	धनबाद जिला, झारखण्ड में स्थित भारत कोकिंग कोल लिमिटेड के क्लस्टर VII कोयला खनन परियोजना की पर्यावरण स्वीकृति जिसका कुल क्षेत्र 2127.70 हेक्टेयर है एवं उत्पादन क्षमता 11.42 मिलियन टन प्रति वर्ष है को संशोधित किया गया है जिसमें राजापुर/द-झरिया ओसीपी परियोजना की पीक उत्पादन क्षमता 2.56 एमटीपीए की गयी है पर क्लस्टर VII की उत्पादन क्षमता 11.42 मिलियन टन प्रति वर्ष यथावत है।	J-11015/238/ 2010-IA-II (M) Pt. दिनांक 20 अगस्त 2020
पर्यावरणीय स्वीकृति प्रतिलिपि झारखंड राज्य प्रदूषण नियंत्रण बोर्ड के पास उपलब्ध है तथा इसे पर्यावरण एवं वन मंत्रालय की अधिकारिक वेबसाइट http://envfor.nic.in और भारत कोकिंग कोल लिमिटेड के आधिकारिक वेबसाइट http://www.bcciweb.in पर देखा जा सकता है।		
ह०/- विभागाध्यक्ष (पर्यावरण), कोयला भवन		



Picture 1 – Covered Transportation



Picture 2 – Water Sprinkling on Transportation Road



Dhanbad, Jharkhand, India



Longitude Latitude

86.4098° E 23.7752° N



36° C

Tuesday, 26, Jul, 2022

10:20 AM



Picture 3 – Manual Sweeping of Public Road



भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन, नदी विकास
और गंगा संरक्षण विभाग
केंद्रीय भूमि जल प्राधिकरण
Government of India
Ministry of Jal Shakti
Department of Water Resources,
River Development & Ganga Rejuvenation
Central Ground Water Authority

(भूजल निकासी हेतु अनापत्ति प्रमाण पत्र)

NO OBJECTION CERTIFICATE (NOC) FOR GROUND WATER ABSTRACTION

Project Name:	Cluster Vii Group Of Mines Of Bccl		
Project Address:	Office Of The General Manager, Kusunda Area, Bccl		
Town:	Dhanbad (m Corp.)	Block:	Dhanbad
District:	Dhanbad	State:	Jharkhand
Pin Code:			
Communication Address:	Office Of The General Manager, Kusunda Area, Bccl, Dhanbad, Dhanbad, Jharkhand - 828116		
Address of CGWB Regional Office :	Central Ground Water Board Mid Eastern Region, 6th & 7th Floor, Lok Nayak Jai Prakash Bhawan, Frazer Road Dak Banglow, Patna, Bihar - 800011		

1. NOC No.:	CGWA/NOC/MIN/ORIG/2021/13617		
2. Application No.:	21-4/274/JH/MIN/2018	3. Category:	Sem. Critical
4. Project Status:	Existing Project	5. NOC Type:	New
6. Valid from:	02/11/2021	7. Valid up to:	01/11/2023
8. Ground Water Abstraction Permitted:			

Picture 4 – Ground Water NOC Cluster VII



Picture 5 – Training at Vocational Training Centre



Picture 6 – Spreading Seed Ball on OB Dumps



Picture 7 – Enclosed Coal Handling Plant



Picture 8 – Top Soil Stack



Picture 9 – Green Belt Development along Railway Siding



Picture 10 – Oil & Grease Trap



Picture 11 – Grassing on active OB Dumps



Picture 12 – Piezometer well



Picture 13 – Skill training to PAPs