

			<p style="text-align: center;">भारत कोकिंग कोल लिमिटेड BHARAT COKING COAL LIMITED (एक मिनी रत्न कम्पनी) A Mini Ratan Company महाप्रबंधक का कार्यालय Office of the General Manager Civil Department लोदना क्षेत्र-10 Lodna Area-X Email – gmlodna.bccl@coalindia.in</p>
---	---	--	---

Ref. No. BCCL/LA/CIVIL/NIQ/2024-25/ 46

Date: 23.10.2024

QUOTATION INVITING NOTICE

1. Sealed quotations in Single envelope are invited from eligible contractors for the following work.:-

SL. No.	Description of work	Amount Including GST (In Rs.)	Earnest Money (In Rs.)	Period of Completion (In days)
01	Repairing of Boundary wall at MOCP Sector-I under Lodna Area	175601.27	2200.00	20
02	Repairing of quarter of Binita Jha quarter situated at Pirkubandh under Lodna Area	58276.31	800.00	20
03	Repairing and cleaning of drain at MOCP Sector-III under Lodna Area	157769.07	2000.00	20
04	Repairing of damaged dain and compound wall Doctors Colony Jealgora under Lodna Area	153083.37	2000.00	20
05	Repairing and Maintenance of NHS quarter of Sri Sukadeo Paswan quarter situated at Bhaga under Lodna Area	60849.69	800.00	20
06	Providing and Laying of Pipe Line from Lodna Filter Plant to Lodna Teacher Colony Lodna Colliery under Lodna Area	199649.94	2500.00	20
07	Repairing of damaged drain of Staff Colony behind NHS quarter at Pirkubandh Bhaga No.4 under Lodna Area	89157.73	1200.00	20
08	P/Fixing damaged Pit water Pipe Line from Lodna 6 no. Tank to Lodna 6 no. Muhallah at Lodna Colliery under Lodna Area	190348.93	2400.00	20
09	Cleaning of Septic Tank and Partial Portion of Sanitary fitting at G.M Bungalow situated at near Denobli More under Lodna Area	77401.45	1000.00	20
10	Repairing and Maintenance of Sri Dinanath Pandey quarter situated at Baniahir under Lodna Area	49773.93	700.00	20
11	Repairing of quarter of Sidheswar Yadav and Anil Choudhary quarter situated at Dumariatand BCCL New Colony under Lodna Area	167617.29	2100.00	20
12	Repairing and Maintenance of NHS quarter 1. MD. Habibullah Khan and 2. Azil Ahamad quarter situated at Baniahir under Lodna Area	142847.85	1800.00	20
13	Repairing of quarter Sri Bhagwan Mistri quarter situated at Bararee More under Lodna Area	73844.16	1000.00	20
14	Repairing and Cleaning of drain at Dangalchowrah near Denobli More under Lodna Area	157173.65	2000.00	20

SL. No.	Description of work	Amount Including GST (In Rs.)	Earnest Money (In Rs.)	Period of Completion (In days)
15	Garbage cleaning and laying spreading and compacting of road potholes at Lodna More to Santoshi Mandir under Lodna Area	28086.77	400.00	20
16	Repairing of Pipe Line of Sri Amit Kumar Yadav quarter situated near JLN Stadium 'B' type under Lodna Area	30817.41	400.00	20
17	Repairing of Collapse compound wall at Jealgora Hospital under Lodna Area	103248.30	1300.00	20
18	Providing of Chabutra at 6 no. incline NT-ST under Lodna Area	71917.26	900.00	20

Note: There will be 100% exemption of EMD deposit for the Co-operative Societies constituted of local land losers/Project affected Persons (PAPs). PAPs who have not been given any employment will only be eligible for being a member of the co-operative society. The co-operative society will be formed of the PAPs only. The co-operative should be registered under relevant act and to comply with rules and regulations made there under. A certificate that such co-operatives formed consists of only PAPs who have not been provided any employment by BCCL has to be obtained from the L&R Dept. of BCCL, HQ

2. Quotation documents can be obtained from the website of Bharat Coking Coal Limited i.e. <https://www.bcclweb.in>.

Note:

- In case of Partnership firm, the undertaking must be signed by all the partners of the Partnership Firm.*
- In case of Project Affected Person(s) (PAPs) firms, this document is to be signed by all the partners of the PAPs who have formed Partnership firm and if the PAPs have formed co-operative society, this document is to be signed by any legally acceptable authorized signatory of the co-operative society, approved through the Resolution of the co-operative society.*

The quotation documents will be available in the website of Bharat Coking Coal Limited under Tenders and Notices icon/option and can be downloaded from the "Tenders below 2 lakhs" window form **dt 28.10.2024 to dt 02.11.2024** Quotations will be received from **10.00AM to 05.00 PM on dt 02.11.2024** in the prescribed quotation box installed in the Office of the Civil Dept., Lodna Area Office

3. The Envelope containing Bid document i.e. Confirmatory documents, Earnest money deposit as well as price bid of the quotation, will be opened **on 04.11.2024 at 11.00 AM** in the presence of the attending bidders or their authorized representatives whosoever chooses to be present in the office of the undersigned only. In case of holiday on opening date, it will be opened on the next working day at the same time and same place.

4. Earnest Money Deposit (EMD):

Earnest money can be deposited in the form of Bank Draft/Banker's certificate cheque or Banker's Pay Order drawn in favour of "Bharat Coking Coal Limited, (Dhanbad or respective Area of BCCL as applicable)" on any Nationalized Bank Payable at "Dhanbad (or respective Area of BCCL as applicable). The Purchaser's name should not appear on the Banker's Cheque or Banker's Pay Order.

Quotation without earnest money shall be rejected.

No EMD is required to be submitted by the Co-operative Societies formed by PAPs as mentioned in the Note at Clause no. 1.

5. The interested bidders must submit the following documents and credentials in sealed envelope:-

- i. Copy of Permanent Account Number (PAN) issued by Income Tax department, Govt. of India
- ii. Undertaking by Bidder/s on his/her/their Letter Head regarding genuineness of the copy of documents submitted by him in support of his eligibility as per the format given in the bid document at Annexure-I.
- iii. The following documents depending upon the status w.r.to GST as declared by Bidder in the

BOQ sheet:

a) Status: GST Registered Bidder under regular scheme

Document: GST Registration Certificate (i.e. GST identification Number) issued by appropriate authority of India.

OR

b) Status: GST Registered Bidder under composition scheme

Document: GST Registration Certificate (i.e. GST identification Number) issued by appropriate authority of India.

OR

c) Status: GST unregistered bidder:

Document: A Certificate from a practicing Chartered Accountant having membership number with Institute of Chartered Accountants of India certifying that the bidder is GST unregistered bidder in compliance with the relevant GST rules of India.

Note:

If turnover of bidder exceeds exemption/threshold limit, the bidder must have GST registration as per GST Act and rules.

6. The rate (excluding GST) is to be quoted in both figures and words. Conditional quotations will not be accepted unless specified.

7. All pages of the documents and credentials to be submitted by the bidder

must be **self-authenticated** by the bidder /constituted attorney of the bidder with his signature and seal. Completed and sealed Envelope of quotation documents should contain following:-

- i. The statutory documents & all other documents as stated in this QUOTATION NOTICE and else wherein the quotation document.
- ii. The Bill of quantity and the abstract sheet after duly filling the quoted rates i.e. the "Price-Bid".
- iii. Earnest Money Deposit in any of the form as defined at clause no.4.

*The documents, EMD & BOQ should be submitted in a sealed envelope with appropriate superscription.

8. Quotations shall be rejected outright without any reference if the documents submitted by the bidder along with their quotation fail to prove eligibility in terms of criteria as per Clause no. 5 of this tender notice. Documents submitted along with the quotations shall be final and no supplementary document shall be accepted unless asked by the Company.

9. The General Terms and conditions of latest Civil Engineering Manual of CIL (with Amendments, if any) shall be applicable for this tender which can be accessed from Coal India web site www.coalindia.in

10. Taxes and Duties:

All duties, taxes (excluding Goods and Services Tax (GST) & GST Compensation Cess (if applicable) only) and other levies, royalty, building and construction workers cess (as applicable in States) payable by the bidder/Contractor under the Contract, or for any other cause as applicable on the last date of submission of Bid, shall be included in the rates, prices and the total Bid Price submitted by the Bidder. Applicable GST, if any, either payable by bidder or by company under reverse charge mechanism shall be calculated on the basis of applicable GST rate mentioned in the BOQ.

[Note (For departmental users only & not to be part of Tender Document):

- 1. Applicable rate of GST shall be mentioned in the BOQ.**
- 2. Applicability of INPUT TAX CREDIT (ITC) to the Company shall be mentioned in the BOQ.]**

:4:-

All investments, operating expenses, incidentals, overheads, leads, lifts, carriages, tools and plants etc. as may be attendant upon execution and completion of works shall also be included in the rates, prices and total Bid price submitted by the bidder.

However, such duties, taxes, levies etc. which is notified after the last date of submission of Bid and/or any increase over the rate existing on the last date of submission of Bid shall be reimbursed by the company on production of documentary evidence in support of payment actually made to the concerned authorities.

Similarly, if there is any decrease in such duties, taxes and levies the same shall become recoverable from the contractor. The details of such duties, taxes and other levies along with rates shall be declared by the bidder.

The item wise rate quoted by bidder shall be inclusive of all taxes, duties & levies but excluding GST & GST Compensation Cess, if applicable. The payment of GST and GST Compensation Cess by service availer (i.e. BCCL) to bidder/contractor (if GST payable by bidder/contractor) would be made only on the latter submitting a Bill/invoice in accordance with the provision of relevant GST Act and the rules made there under and after online filing of valid return on GST portal. Payment of GST & GST Compensation Cess is responsibility of the service provider/contractor.

Further, any GST credit note required to be issued by the bidder / contractor under the GST provisions should be issued within the time limit prescribed under the GST law. However, in case bidder/contractor is GST unregistered bidder/dealer or GST registered under composition scheme in compliance with GST rules, the bidder/dealer shall not charge any GST and/or GST Compensation Cess on the bill/invoice. In case of unregistered dealer/bidder, GST, if applicable will be deposited by BCCL directly to concerned authorities in terms with GST provisions.

Input tax credit is to be availed by BCCL as per rule.

If BCCL fails to claim Input Tax Credit(ITC) on eligible Inputs, input services and Capital Goods or the ITC claimed is disallowed due to failure on the part of supplier/vendor of goods and services in incorporating the tax invoice issued to BCCL in its relevant returns under GST, payment of CGST & SGST or IGST, GST (Compensation to State) Cess shown in tax invoice to the tax authorities, issue of proper tax invoice or any other reason whatsoever, the applicable taxes & cess paid based on such Tax invoice shall be recovered from the current bills or any other dues of the supplier/vendor along with interest and penalty, if any.

The rates and prices quoted by the Bidder shall be fixed for the duration of the contract and shall not be subject to variations on any account except to the extent variations allowed as per the conditions of the contract of the bidding document. The company reserves the right to deduct/ withhold any amount towards taxes, levies, etc. and to deal with such amount in terms of the provisions of the Statute or in terms of the direction of any statutory authority and the company shall only provide with certificate towards such deduction and shall not be responsible for any reason whatsoever.

In case of collection of minor minerals in area (both virgin and non-virgin), acquired by the Company under the Coal Act, the contractor will have to produce a royalty clearance certificate from the District Authorities before full and final payment. Further, where any damages or compensation becomes payable by either the Company or the bidder / contractor pursuant to any provision of this Agreement, appropriate GST wherever applicable as per the GST provisions in force shall also apply in addition to such damages or compensation.

11. System for decision of L1 bidder

Case – 1: Supply for which INPUT TAX CREDIT (ITC) is not available to the Company.

For calculation of Overall Bid Value, the GST [CGST, SGST/UTGST, IGST and GST (compensation to state tax)] to be paid by the bidder or by BCCL will be added to decide the L1 i.e. the ranking of the Bidders will be decided based on rates quoted by the bidders plus GST. This value of the bidder will be “the Cost to Company”.

Then share of GST to be deposited by BCCL, if any will be deducted from overall bid value to arrive at the Contract value. The Price-bids of the bidders shall have no condition. The Price Bid which is incomplete and not submitted as per instruction given above is liable for rejection.

Case – 2: Supply for which INPUT TAX CREDIT (ITC) is available to the Company.

For calculation of Overall Bid Value, the GST [CGST, SGST/UTGST, IGST and GST (compensation to state tax)] to be paid by the Bidder or by BCCL will be ignored to decide the L1 i.e. the ranking of the Bidders will be decided based on rates quoted by the bidders excluding GST. This value of the bidder will be “the cost to Company”.

Then share of GST to be paid by bidder shall be added with overall bid value to arrive at the Contract value. The Price-bids of the bidders shall have no condition. The Price Bid which is incomplete and not submitted as per instruction given above is liable for rejection.

Note: The bidder should mention their GST category in the BOQ as per clause 5. iii of this Tender Notice.

12. Price variation will be/not be applicable for this work. (Delete whichever is not applicable)

13. Bid Validity:

The validity period of the quotations shall be **120(One Hundred Twenty)** days from the end date of bid submission.

14. Prohibition of Child Labour engagement:

The contractor/contractual Agencies must not engage any Child Labour during the course of execution of the contract work within the meaning and scope of the Child Labour Prohibition & Regulation Act-1986 and its relevant Act and Rules amended from time to time by the Govt. of India.

15. Implementation of CMPF:

The bidder shall have to ensure implementation of CMPF, if applicable, in respect of the workers deployed by him.

16. Settlement of Disputes:

Matters relating to any dispute or difference arising out of this quotation and subsequent contract Awarded based on this quotation, shall be subject to the jurisdiction of District Court, (City/Town), of Dhanbad.

17. BCCL reserves its right to accept or reject any or all the quotations without assigning any reason whatsoever or to distribute the work amongst the bidders.

Quotation Inviting Authority

प्रतिलिपि -

1. सी.वी. ओ, बीसीसीएल कोयला भवन, धनबाद
2. महाप्रबंधक(असैनिक), बीसीसीएल, कोयला नगर, धनबाद
3. मुख्य महाप्रबंधक/महाप्रबंधक, सभी क्षेत्र/परियोजना, अंतर्गत बीसीसीएल
4. महाप्रबंधक, लोदना क्षेत्र
5. अवर महाप्रबंधक, लोदना क्षेत्र
6. क्षेत्रीय प्रबन्धक(कार्मिक), लोदना क्षेत्र
7. क्षेत्रीय प्रबन्धक(वित्त)/केशियर, लोदना क्षेत्र
8. परियोजना पदाधिकारी, सभी इकाई, लोदना क्षेत्र
9. निविदा समिति सदस्य, लोदना क्षेत्र
10. बिल्डर्स एसोसिएशन ऑफ इंडिया, 316 एलआईजी, हाउसिंग कॉलोनी, धनबाद
11. सूचना पट्ट
12. कार्यालय प्रति

प्रतिलिपि -

एरिया मैनेजर ईडीपी (सिस्टम)लोदना रीजनल स्टोर कृपया बीसीसीएल वेब साइट पर अपलोड करें

Annexure-I
UNDERTAKING & BID SECURITY DECLARATION

I _____ Proprietor/Partner/Legal Attorney/Director/ Accredited Representative of
M/S _____ solemnly declare that:

1. I/We am/are submitting Bid for the work _____ against
Quotation Notice No _____ and I/we offer to execute the work in accordance
with all the terms, conditions and provisions of the Quotation Notice.

2. Myself/Our Partners/ Directors don't has/have any relative as employee of **Bharat Coking Coal Limited.**

OR

The details of relatives of Myself/Our Partners/Directors working as employee of **Bharat Coking Coal Limited** is
as follows:

- a) Name of the employee
- b) Place of posting
- c) Department
- d) Designation
- e) Type of relation – Wife/Husband/ Father/ Step-Father/Mother / Step-Mother/ Son/Step-son/
Son's wife / Daughter / Daughter's Husband / Brother/ Step-Brother/ Sister / Step-Sister.

3. All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this
Bid is complete, correct and true.

4. All copy of documents, credentials and documents submitted along with this Bid are genuine, authentic, true and
valid.

5. I/ We hereby authorize department to seek references / clarifications from our Bankers.

6. We hereby undertake that we shall register and obtain license from the competent authority under the contract
labour (Regulation & Abolition Act) as relevant, if applicable.

7. I/We hereby undertake that we shall take appropriate steps for registration as relevant under CMPF authorities, if
applicable. We shall make necessary payments as required under law.

Or

*I/We hereby undertake that we shall take appropriate steps for registration as relevant under CMPF authorities, if
applicable. We shall make necessary payments as required under law.

*** Delete whichever is not applicable.**

8. ** I/We have not been banned or delisted by any Govt., or Quasi Govt. Agencies or PSUs.

Or

**I / Wehave been banned by the organization named “_____” for a period
of..... year/s, effective from to.....

**** Delete whichever is not applicable.**

9. I/We do not have relationship with any other participating bidders, directly or through common third parties, that
puts us in a position to have access to information about or influence on the bid of another Bidder.

10. I/We or any of my/our affiliate has/have not participated as consultant in the preparation of the design or
technical specification of the contract that is the subject of the bid.

11. If any information and document submitted is found to be false/ incorrect at any time, department may cancel
my/our Bid and action as deemed fit may be taken against me/us, including termination of the contract, forfeiture of
all dues including Earnest Money and banning of our firm and all partners of the firm etc as per the tender
document.

Note:

- 1. If the bidder is a partnership firm, this document must be signed by all the partners.
- 2. In case of Project Affected Person(s) (PAPs) firms, this document is to be signed by all the partners of the PAPs
who have formed Partnership firm and if the PAPs have formed cooperative society, this document is to be signed
by any legally acceptable authorized signatory of the co-operative society, approved through the Resolution of the
co-operative society.

Name of work: - “Repairing of Boundary wall at MOCP Sector-I under Lodna Area”.

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	A.R	B/work	9.90	M3	5435.75	53813.93
2	A.R	B/work (1:6) S/ST	6.58	M3	5791.91	38110.77
3	13.1.2	FINISHING 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	100.00	M2	222.00	22200.00
4	A.R	Colour Washing	357.00	M2	22.29	7957.53
5	10.2	STEEL WORK Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	180.00	KG	88.20	15876.00
6	4.1.8	CONCRETE WORK Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).	2.12	M3	5120.95	10856.41
						148814.64
					GST @ 18 %	26786.63
					Grand total	175601.27

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work: - Repairing of quarter of Binita Jha quarter situated at Pirkubandh under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	13.16.1	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand).	10.00	M2	198.20	1982.00
2	13.1.2	FINISHING 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	30.00	M2	222.00	6660.00
3	13.90.1	Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	160.00	M2	46.25	7400.00
4	13.99.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	22.00	M2	68.30	1502.60
5	A.R	C/washing	100.00	M2	22.65	2265.00
6	10.25.2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	126.00	KG	115.05	14496.30
	A.R	25mm thick C.C	40.00	M2	377.02	15080.80
						49386.70
					GST @ 18 %	8889.61
					Grand total	58276.31

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work: - Repairing and cleaning of drain at MOCP Sector-III under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	126.02	M3	154.90	19520.50
2	1.1.3	Transporting of Sludge	88.00	M3	114.06	10037.28
3	A.R	B/work (1:6) F/P	6.89	M3	5349.86	36860.54
4	13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix :1:4 (1 cement: 4 fine sand)	181.22	M2	288.25	52236.67
5	A.R	25mm thick C.C	39.03	M2	385.54	15047.63
						133702.60
					GST @ 18 %	24066.47
					Grand total	157769.07

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work: - Repairing of damaged drain and compound wall Doctors Colony Jealgora under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	A.R	B/work (1:6) F/P	9.52	M3	5281.11	50276.17
2	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	25.00	M3	154.90	3872.50
3	A.R	C/washing	293.68	M2	22.65	6651.85
4	13.1.2	FINISHING 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	150.00	M2	222.00	33300.00
5	13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	61.00	M2	288.25	17583.25
6	1.1.3	Transporting of Sludge	45.85	M3	114.06	5229.65
7	10.25.2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	90.00	KG	115.05	10354.50
8	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	75.00	M2	32.85	2463.75
						129731.67
					GST @ 18 %	23351.70
					Grand total	153083.37

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Repairing and Maintenance of NHS quarter of Sri Sukadeo Paswan quarter situated at Bhaga under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	A.R	Removal of Tarfelting	40.89	M2	82.85	3387.74
2	4.1.3	CONCRETE WORK Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources).	1.55	M3	6086.45	9434.00
3	14.87	Providing and laying in situ five course water proofing treatment with APP (Atactic Polypropylene) modified Polymeric memberane over roof consisting of first coat of bitumen primer @ 0.40 litre per sqm, 2nd & 4th courses of bonding material @ 1.20 kg/sqm, which shall consist of blown type bitumen of grade 85/25 conforming to IS : 702, 3rd layer of roofing membrane APP modified Polymeric membrane 2.0 mm thick of 3.00 Kg/ sqm weight consisting of five layers prefabricated with centre core as 100 micron HMHDPE film sandwiched on both sides with polymeric mix and the polymeric mix is protected on both side with 20 micron HMHDPE film. 5th, the top most layer shall be finished with brick tiles of class designation 10 grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% integral water proofing compound by weight of cement over a 12 mm layer of cement mortar 1:3 (1 cement : 3 fine sand) and finished neat (item of laying brick tiles shall be paid for separately).	40.89	M2	355.65	14542.53
4	13.16.1	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	15.00	M2	198.20	2973.00
5	13.1.2	FINISHING 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	20.00	M2	222.00	4440.00
6	A.R	C/washing	80.00	M2	22.65	1812.00
7	13.87.1	White washing with lime to give an even shade : Old work (two or more coats)	120.00	M2	14.70	1764.00
	10.25.2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	90.00	KG	115.05	10354.50
	15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.04	M3	1457.35	58.29
8	A.R	25mm thick C.C	7.43	M2	377.05	2801.48
						51567.54
					GST @ 18 %	9282.16
					Grand total	60849.69

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work: - Providing and Laying of Pipe Line from Lodna Filter Plant to Lodna Teacher Colony
Lodna Colliery under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	18.13.2	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 50 to 80 mm nominal bore	1.00	nos.	1257.90	1257.90
2	A.R	50m dia UPVC Pipe	390.00	M2	374.08	145891.20
3	18.9.2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 20 mm nominal dia Pipes	75.00	M2	217.40	16305.00
4	18.9.1	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 15 mm nominal dia Pipes	5.00	M2	173.25	866.25
5	18.46.6	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 50 mm nominal bore	4.00	M2	523.95	2095.80
6	A.R	B/work (1:6) F/P	0.25	M3	5349.86	1337.47
7	13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	5.00	M2	288.25	1441.25
						169194.87
					GST @ 18 %	30455.08
					Grand total	199649.94

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Repairing of damaged drain of Staff Colony behind NHS quarter at Pirkubandh Bhaga No.4 under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	2.6.1 (+) 2.24.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil (+) Extra rates for quantities of works, executed: In or under water and/or liquid mud, including pumping out water as required	10.00	M3	185.88	1858.80
2	A.R	B/work (1:6 F/P	7.46	M3	5349.86	39909.96
3	A.R	25mm flooring	10.00	M2	385.54	3855.40
4	13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	91.31	M2	288.25	26320.11
5	1.1.3	Transporting of Sludge	18.53	M3	114.06	2113.53
6	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	45.65	M2	32.85	1499.60
						75557.40
					GST @ 18 %	13600.33
					Grand total	89157.73

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- P/Fixing damaged Pit water Pipe Line from Lodna 6 no. Tank to Lodna 6 no. Muhallah at Lodna Colliery under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	18.13.2	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 50 to 80 mm nominal bore	1.00	NO	1257.90	1257.90
2	18.9.6	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 50 mm nominal dia Pipes	230.00	M3	684.50	157435.00
3	18.46.6	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 50 mm nominal bore	5.00	NO	523.95	2619.75
						161312.65
					GST @ 18 %	29036.28
					Grand total	190348.93

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Cleaning of Septic Tank and Partial Portion of Sanitary fitting at G.M Bungalow situated at near Denobli More under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	A.R	Cleaning of Septic Tank	17.41	M3M3	711.39	12385.30
2	15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	3.65	M3	1232.80	4499.72
3	15.3	DISMANTLING AND DEMOLISHING Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	0.42	M3	2126.10	892.96
4	A.R	B/work (1:6) F/S/ST	1.59	M2	5832.69	9273.98
5	13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	16.93	M2	288.25	4880.07
6	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	3000.00	L	7.65	22950.00
7	18.9.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 32 mm nominal dia Pipes	6.10	M	356.30	2173.43
8	18.9.3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 25 mm nominal dia Pipes	12.19	M	280.75	3422.34
9	18.17.1	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	4.00	NO.	489.65	1958.60
10	18.13.1	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	2.00	NO.	595.00	1190.00
11	A.R	25mm floor (1:2:4)	5.22	M2	377.02	1968.04
						65594.45
					GST @ 18 %	11807.00
					Grand total	77401.45

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Repairing and Maintenance of Sri Dinanath Pandey quarter situated at Baniahir under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	14.87	Providing and laying in situ five course water proofing treatment with APP (Atactic Polypropylene) modified Polymeric memberane over roof consisting of first coat of bitumen primer @ 0.40 litre per sqm, 2nd & 4th courses of bonding material @ 1.20 kg/sqm, which shall consist of blown type bitumen of grade 85/25 conforming to IS : 702, 3rd layer of roofing membrane APP modified Polymeric membrane 2.0 mm thick of 3.00 Kg/sqm weight consisting of five layers prefabricated with centre core as 100 micron HMHDPE film sandwiched on both sides with polymeric mix and the polymeric mix is protected on both side with 20 micron HMHDPE film. 5th, the top most layer shall be finished with brick tiles of class designation 10 grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% integral water proofing compound by weight of cement over a 12 mm layer of cement mortar 1:3 (1 cement : 3 fine sand) and finished neat (item of laying brick tiles shall be paid for separately).	40.00	M2	355.65	14226.00
2	A.R	25mm thick C.C (1:2:4)	17.61	M2	377.05	6639.85
3	13.16.1	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	15.00	M2	198.20	2973.00
4	13.1.2	FINISHING 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	20.00	M2	222.00	4440.00
5	A.R	Cleaning of Septic Tank	5.00	M2	711.39	3556.95
6	13.90.1	Distempering with 1st quality acrylic distember (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	150.00	M2	46.25	6937.50
7	13.99.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	30.00	M2	68.30	2049.00
8	A.R	C/washing (Old)	60.00	M2	22.65	1359.00
						42181.30
					GST @ 18 %	7592.63
					Grand total	49773.93

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Repairing of quarter of Sidheswar Yadav and Anil Choudhary quarter situated at Dumariatand BCCL New Colony under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	22.14.1	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	3.11	M3	6202.55	19289.93
2	A.R	Removal of Tarfelt	81.78	M2	81.27	6646.26
3	13.16.1	6 mm cement plaster of mix :1:3 (1 cement : 3 fine sand)	20.00	M2	198.20	3964.00
4	13.1.2	FINISHING 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	60.00	M2	222.00	13320.00
5	A.R	25mm thick C.C	76.11	M2	372.43	28345.65
6	15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	1.52	M3	1457.35	2215.17
7	12.15.1	Painting top of roofs with bitumen of approved quality @ 17kg per 10 sqm impregnated with a coat of coarse sand at 60 cudm per 10 sqm, including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete : With residual type petroleum bitumen of grade VG -10	40.89	M2	106.00	4334.34
8	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	30.00	M2	32.85	985.50
9	10.25.2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	288.00	KG	115.05	33134.40
10	13.90.1	Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	320.00	M3	46.25	14800.00
11	13.99.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	46.00	M2	68.30	3141.80
12	13.43.1	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	160.00	M2	53.30	8528.00
13	A.R	C/wash	150.00	M2	22.29	3343.50
						142048.55
					GST @ 18 %	25568.74
					Grand total	167617.29

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Repairing and Maintenance of NHS quarter 1. MD. Habibullah Khan and 2. Azil Ahamad quarter situated at Baniahir under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	22.14.1	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	3.11	M3	6202.55	19289.93
2	13.1.2	FINISHING 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	90.00	M2	222.00	19980.00
3	13.16.1	6 mm cement plaster of mix :1:3 (1 cement : 3 fine sand)	40.72	M2	198.20	8070.70
4	A.R	25mm thick C.C	54.00	M2	372.43	20111.22
5	13.99.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	59.00	M2	68.30	4029.70
6	10.25.2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	200.00	KG	115.05	23010.00
7	13.90.1	Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	300.00	M2	46.25	13875.00
8	A.R	C/wash	160.00	M2	22.29	3566.40
9	12.41.2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	31.00	M	265.05	8216.55
10	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	4.24	M3	214.15	908.00
						121057.50
					GST @ 18 %	21790.35
					Grand total	142847.85

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Repairing of quarter Sri Bhagwan Mistri quarter situated at Bararee More under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	15.3	DISMANTLING AND DEMOLISHING Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge	0.35	M3	2126.10	744.14
2	5.1.2	REINFORCED CEMENT CONCRETE Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, ifinishing and reinforcement- All work up to plinth level : 1:1.5:3 (1 cement: 1.5 coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources). .	0.35	M3	6856.30	2399.71
3	5.22.3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Cold twisted bars	28.00	KG	75.65	2118.20
4	A.R	25mm thick C.C (1:2:4)	25.00	M2	372.43	9310.75
5	A.R	Brick Flat Soling	25.00	M2	356.91	8922.75
6	A.R	Brick work (1:6) F/P	0.64	M3M2	5244.54	3356.51
	13.16.1	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	15.00	M2	198.20	2973.00
	13.1.2	FINISHING 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	20.00	M2	222.00	4440.00
	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	35.00	KG	32.85	1149.75
	10.25.2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	90.00	M2	115.05	10354.50
	13.90.1	Distempering with 1st quality acrylic distember (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	140.00	M2	46.25	6475.00
	13.85.3	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	70.00	M2	53.30	3731.00
	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	70.00	M2	12.05	843.50
	13.99.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	30.00	M2	68.30	2049.00
7	13.109.2	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete.	80.00	M2	46.40	3712.00
						62579.80
					GST @ 18 %	11264.36
					Grand total	73844.16

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Repairing and Cleaning of drain at Dangaldhowrah near Denobli More under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	131.36	M3	154.90	20347.66
2	2.6.1	Extra rates for quantities of works, executed: In or under water and/or liquid mud, including pumping out water as required	26.27	M3	154.90	4069.22
3	1.1.3	Carriage of sludge materials	131.36	M3	114.06	14982.92
4	13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	60.00	M2	288.25	17295.00
5	5.12	Providing, hcisting and fixing above plinth level up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but, excluding cost of reinforcement, with 1:1.5:3 (1 cement 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	3.18	M3	7886.35	25078.59
6	5.22.3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Cold twisted bars	230.00	KG	75.65	17399.50
7	A.R	B/work (1:6) F/P	6.36	M3	5349.86	34025.11
						133198.01
					GST @ 18 %	23975.64
					Grand total	157173.65

% Rate quoted by the tenderer_____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work: - Garbage cleaning and laying spreading and compacting of road potholes at Lodna More to Santoshi Mandir under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	16.4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density	29.02	M2	651.00	18892.02
2	2.6.1	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density	31.70	M3	154.90	4910.33
						23802.35
					GST @ 18 %	4284.42
					Grand total	28086.77

% Rate quoted by the tenderer_____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Repairing of Pipe Line of Sri Amit Kumar Yadav quarter situated near JLN Stadium 'B' type under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	18.9.3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 25 mm nominal dia Pipes.	35.00	M	280.75	9826.25
2	18.13.1	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	1.00	NO	277.35	277.35
3	18.9.2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 20 mm nominal dia Pipes	6.00	M	217.40	1304.40
4	18.46.3	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 25 mm nominal bore	2.00	NO	298.70	597.40
5	4.1.3	CONCRETE WORK Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources).	1.00	M3M2	4514.05	4514.05
6	18.17.1	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	1.00	NO	489.65	489.65
	15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	1.00	M3M2	1457.35	1457.35
	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1000.00	L	7.65	7650.00
						26116.45
					GST @ 18 %	4700.96
					Grand total	30817.41

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Repairing of Collapse compound wall at Jealgora Hospital under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	2.86	M3	1232.80	3525.81
2	13.1.2	FINISHING 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	60.00	M2	222.00	13320.00
3	A.R	B/work (1:6) F/P	9.21	M3	5349.86	49272.21
4	4.1.8	CONCRETE WORK Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).	1.41	M3	5120.95	7220.54
5	13.109.1	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 liters/10 sqm complete including cost of Priming coat.	200.00	M2	70.80	14160.00
						87498.56
					GST @ 18 %	15749.74
					Grand total	103248.30

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date

Name of work:- Providing of Chabutra at 6 no. incline NT-ST under Lodna Area

SI.NO	ITEM CODE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE AS PER BCCL SOR	AMOUNT
1	A.R	Brick work (1:6) F/P	7.02	M3	5349.86	37556.02
2	13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	23.04	M2	288.25	6641.28
3	A.R	Brick Flat Soling	22.30	M3	365.56	8151.99
4	A.R	25mm thick C.C	22.30	M2	385.54	8597.54
						60946.83
					GST @ 18 %	10970.43
					Grand total	71917.26

% Rate quoted by the tenderer _____

To be written (Both in words and figures/whether at par/above/below the estimated Value)

(_____)

Name of Contractor
Signature of Contractor
Seal & Date